API Well Number: 43047526500000

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3
AMENDED REPORT ☑

APPLICATION FOR PERMIT TO DRILL

1. WELL NAME and NUMBER NBU 921-22H1CS	
2. TYPE OF WORK DRILL NEW WELL ● REENTER P&A WELL ○ DEEPEN WELL ○	**3. FIELD OR WILDCAT** NATURAL BUTTES
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO	**5. UNIT or COMMUNITIZATION AGREEMENT NAME** NATURAL BUTTES
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.	**7. OPERATOR PHONE** 720 929-6515
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217	**9. OPERATOR E-MAIL** julie.jacobson@anadarko.com
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU 010950-A	**11. MINERAL OWNERSHIP** FEDERAL ● INDIAN ○ STATE ○ FEE ○
	12. SURFACE OWNERSHIP FEDERAL ○ INDIAN ● STATE ○ FEE ○
13. NAME OF SURFACE OWNER (if box 12 = 'fee')	**14. SURFACE OWNER PHONE (if box 12 = 'fee')**
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')	**16. SURFACE OWNER E-MAIL (if box 12 = 'fee')**
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Ute Indian Tribe	**18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS** YES ● (Submit Commingling Application) NO ○
	19. SLANT VERTICAL ○ DIRECTIONAL ● HORIZONTAL ○

20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2179 FNL 637 FEL	SENE	22	9.0 S	21.0 E	S
Top of Uppermost Producing Zone	1740 FNL 494 FEL	SENE	22	9.0 S	21.0 E	S
At Total Depth	1740 FNL 494 FEL	SENE	22	9.0 S	21.0 E	S

21. COUNTY UINTAH	**22. DISTANCE TO NEAREST LEASE LINE (Feet)** 494	**23. NUMBER OF ACRES IN DRILLING UNIT** 800
	25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 319	**26. PROPOSED DEPTH** MD: 11080 TVD: 11043
27. ELEVATION - GROUND LEVEL 4826	**28. BOND NUMBER** WYB000291	**29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE** 43-8496

Hole, Casing, and Cement Information

String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 2820	28.0	J-55 LT&C	0.2	Type V	180	1.15	15.8
							Class G	270	1.15	15.8
PROD	7.875	4.5	0 - 11080	11.6	HCP-110 LT&C	13.0	Premium Lite High Strength	340	3.38	12.0
							50/50 Poz	1580	1.31	14.3

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES

☑ WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	☑ COMPLETE DRILLING PLAN
☐ AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	☐ FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
☑ DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	☑ TOPOGRAPHICAL MAP

NAME Laura Abrams	**TITLE** Regulatory Analyst II	**PHONE** 720 929-6356
SIGNATURE	**DATE** 04/27/2012	**EMAIL** Laura.Abrams@anadarko.com
API NUMBER ASSIGNED 43047526500000	**APPROVAL**	Permit Manager

RECEIVED: May 30, 2012

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 921-22H1CS

Surface: 2179 FNL / 637 FEL SENE
BHL: 1740 FNL / 494 FEL SENE

Section 22 T9S R21E

Unitah County, Utah
Mineral Lease: UTU 010950-A

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. & 2.a **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

Formation	Depth	Resource
Uinta	0 - Surface	
Green River	1,532'	
Birds Nest	1,862'	Water
Mahogany	2,368'	Water
Wasatch	4,894'	Gas
Mesaverde	7,786'	Gas
Sego	10,003'	Gas
Castlegate	10,062'	Gas
MN5	10,443'	Gas
TVD =	11,043'	
TD =	11,080'	

2.c Kerr McGee Oil & Gas Onshore LP (Kerr McGee) will either drill to the the Blackhawk formation, which is part of the Mesaverde formation, or the Wasatch/Mesaverde formation. If Kerr McGee drills to the Blackhawk formation (part of the Mesaverde formation), please refer to MN5 as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr McGee drills to the Wasatch/Mesaverde formation please refer to Sego as the bottom formation. The attached Wasatch/Mesaverde Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the depths the Wasatch/Mesaverde formations are found.

RECEIVED: April 24, 2012

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

6. **Evaluation Program:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

7. **Abnormal Conditions:**

7.a Blackhawk (Part of Mesaverde Formation) Target Formation

Maximum anticipated bottom hole pressure calculated at 11043' TVD, approximately equals 7,288 psi (0.66 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,909 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

7.b Wasach/Mesaverde Target Formation

Maximum anticipated bottom hole pressure calculated at 10003' TVD, approximately equals 6,402 psi (0.64 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,187 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. **Anticipated Starting Dates:**
Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program
Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

RECEIVED: April 24, 2012

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background
In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements
The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements
Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements
Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

RECEIVED: April 24, 2012

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements
KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion
The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

RECEIVED: April 24, 2012

NBU 921-22H Pad

KERR-McGEE OIL & GAS ONSHORE LP

BLACKHAWK DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP			DATE	December 21, 2011
WELL NAME	**NBU 921-22H1CS**			TD	11,043' TVD 11,080' MD
FIELD	Natural Buttes	COUNTY	Uintah	STATE	Utah
FINISHED ELEVATION	4,826'				
SURFACE LOCATION	SENE 2179 FNL 637 FEL Sec 22 T 9S R 21E				
	Latitude: 40.022848 Longitude: -109.530693 NAD 83				
BTM HOLE LOCATION	SENE 1740 FNL 494 FEL Sec 22 T 9S R 21E				
	Latitude: 40.024054 Longitude: -109.530187 NAD 83				
OBJECTIVE ZONE(S)	BLACKHAWK				
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), Ute Indian Tribe (Surface), UDOGM Tri-County Health Dept.				

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			12-1/4	8-5/8", 28#, IJ-55, LTC	Air mist
		200'			
			11.00'	8-5/8", 28#, IJ-55, LTC	Air mist

All water flows encountered while drilling will be reported to the appropriate agencies.

Green River @ 1,532'
Top of Birds Nest @ 1,862'
Mahogany @ 2,368'

Preset f/ GL @ 2,820' TVD

Note: 11" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the acutal depth of the loss zone.

Wasatch @ 4,894'

Mud logging program TBD
Cased hole logging program from TD - surf csg

Mesaverde @ 7,786' TVD

Sego @ 10,003' TVD

Castlegate @ 10,062' TVD

MN5 @ 10,443' TVD

Max anticipated Mud required 13.0 ppg

TD @ 11,043' TVD 11,080' MD

7-7/8" | 4-1/2" 11.6# HCP-110 Ultra DQX/LTC csg | Water / Fresh Water Mud 8.3-13.0 ppg

RECEIVED: April 24, 2012

NBU 921-22H Pad

KERR-McGEE OIL & GAS ONSHORE LP

BLACKHAWK DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL			WT.	GR.	CPLG.	DESIGN FACTORS BURST	COLLAPSE	TENSION LTC	TENSION DQX
CONDUCTOR	14"	0-40'									
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,820	28.00	IJ-55	LTC	1.91	1.42	5.03	N/A
								10,690	8,650	279,000	367,174
PRODUCTION	4-1/2"	0	to	5,000	11.60	HCP-110	DQX	1.19	1.16		3.56
	4-1/2"	5,000	to	11,080'	11.60	HCP-110	LTC	1.19	1.16	4.94	

Surface Casing:

(Burst Assumptions: TD = 13.0 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 9000 psi) 0.66 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT		YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1			+ 0.25 pps flocele					
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
			+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized						
Option 2	LEAD	2,320'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00		3.82
			+ 0.25 pps Flocele + 3% salt BWOW					
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
			+ 0.25 pps flocele					
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION	LEAD	4,390'	Premium Lite II +0.25 pps	340	35%	12.00		3.38
			celloflake + 5 pps gilsonite + 10% gel					
			+ 0.5% extender					
	TAIL	6,690'	50/50 Poz/G + 10% salt + 2% gel	1,580	35%	14.30		1.31
			+ 0.1% R-3					

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER: _____ **DATE:** _____

Nick Spence / Danny Showers / Chad Loesel

DRILLING SUPERINTENDENT: _____ **DATE:** _____

Kenny Gathings / Lovel Young

RECEIVED: April 24, 2012

NBU 921-22H Pad

KerrMcGee

KERR-McGEE OIL & GAS ONSHORE LP
WASATCH/MESAVERDE DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP			DATE	December 21, 2011
WELL NAME	**NBU 921-22H1CS**			TD	10,003' TVD 10,040' MD
FIELD	Natural Buttes	COUNTY Uintah	STATE Utah	FINISHED ELEVATION	4,826'
SURFACE LOCATION	SENE 2179 FNL 637 FEL	Sec 22	T 9S	R 21E	
	Latitude: 40.022848	Longitude: -109.530693		NAD 83	
BTM HOLE LOCATION	SENE 1740 FNL 494 FEL	Sec 22	T 9S	R 21E	
	Latitude: 40.024054	Longitude: -109.530187		NAD 83	
OBJECTIVE ZONE(S)	Wasatch/Mesaverde				
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), Ute Indian Tribe (Surface), UDOGM Tri- County Health Dept.				



RECEIVED: April 24, 2012

NBU 921-22H Pad

KERR-McGEE OIL & GAS ONSHORE LP

WASATCH/MESAVERDE DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL			WT.	GR.	CPLG.	DESIGN FACTORS BURST	COLLAPSE	TENSION LTC	TENSION DQX
CONDUCTOR	14"	0-40'									
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,820	28.00	IJ-55	LTC	1.91	1.42	5.03	N/A
								7,780	6,350		267,035
PRODUCTION	4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	0.98		2.83
								10,690	8,650	223,000	
	4-1/2"	5,000	to	10,040'	11.60	HCP-110	LTC	1.53	1.33	4.71	

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT		YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1			+ 0.25 pps flocele					
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
			+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized						
Option 2	LEAD	2,320'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00		3.82
			+ 0.25 pps Flocele + 3% salt BWOW					
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
			+ 0.25 pps flocele					
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION	LEAD	4,390'	Premium Lite II +0.25 pps	340	35%	12.00		3.38
			celloflake + 5 pps gilsonite + 10% gel					
			+ 0.5% extender					
	TAIL	5,650'	50/50 Poz/G + 10% salt + 2% gel	1,330	35%	14.30		1.31
			+ 0.1% R-3					

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER: Nick Spence / Danny Showers / Chad Loesel **DATE:**

DRILLING SUPERINTENDENT: Kenny Gathings / Lovel Young **DATE:**

RECEIVED: April 24, 2012

EXHIBIT A
NBU 921-22H1CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

RECEIVED: April 24, 2012

T9S, R21E, S.L.B.&M.



NOTES:

▲ = Section Corners Located

1. Well footages are measured at right angles to the Section Lines.
2. G.L.O. distances are shown in feet or chains. 1 chain = 66 feet.
3. The Bottom of hole bears N17°54'39"E 461.70' from the Surface Position.
4. Bearings are based on Global Positioning Satellite observations.
5. Basis of elevation is Tri-Sta "Two Water" located in the NW ¼ of Section 1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.

SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

11-7-11

No.6028691 JOHN R SLAUGH — REGISTERED PROFESSIONAL LAND SURVEYOR — STATE OF UTAH

PROFESSIONAL LAND SURVEYOR
REGISTRATION No. 6028691
STATE OF UTAH

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD: NBU 921-22H

NBU 921-22H1CS
WELL PLAT
1740' FNL, 494' FEL (Bottom Hole)
SE ¼ NE ¼ OF SECTION 22, T9S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH.

609 CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 11-1-11	SURVEYED BY: W.W.	SHEET NO: 3
DATE DRAWN: 8-29-11	DRAWN BY: C.T.C.	
SCALE: 1" = 1000'	Date Last Revised:11-3-11 J.G.C.	3 OF 17

RECEIVED: April 24, 2012

API Well Number: 43047526500000

WELL NAME	SURFACE POSITION					BOTTOM HOLE				
	NAD83		NAD27			NAD83		NAD27		
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	FOOTAGES	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	FOOTAGES
NBU 921-22H4CS	40°01'22.082" 40.022801°	109°31'50.365" 109.530657°	40°01'22.209" 40.022836°	109°31'47.888" 109.529969°	2196' FNL 627' FEL	40°01'20.043" 40.022234°	109°31'48.651" 109.530181°	40°01'20.170" 40.022269°	109°31'46.174" 109.529493°	2403' FNL 494' FEL
NBU 921-22H4BS	40°01'22.167" 40.022824°	109°31'50.430" 109.530675°	40°01'22.294" 40.022859°	109°31'47.953" 109.529987°	2188' FNL 632' FEL	40°01'23.323" 40.023145°	109°31'48.663" 109.530184°	40°01'23.450" 40.023181°	109°31'46.186" 109.529496°	2071' FNL 494' FEL
NBU 921-22H1CS	40°01'22.252" 40.022848°	109°31'50.495" 109.530693°	40°01'22.379" 40.022883°	109°31'48.018" 109.530005°	2179' FNL 637' FEL	40°01'26.593" 40.024054°	109°31'48.675" 109.530187°	40°01'26.720" 40.024089°	109°31'46.198" 109.529499°	1740' FNL 494' FEL
NBU 921-22A4CS	40°01'22.337" 40.022871°	109°31'50.560" 109.530711°	40°01'22.464" 40.022907°	109°31'48.084" 109.530023°	2170' FNL 642' FEL	40°01'31.059" 40.025294°	109°31'48.820" 109.530228°	40°01'31.186" 40.025329°	109°31'46.343" 109.529540°	1288' FNL 504' FEL
NBU 921-22A4BS	40°01'22.422" 40.022895°	109°31'50.626" 109.530729°	40°01'22.549" 40.022930°	109°31'48.149" 109.530041°	2162' FNL 647' FEL	40°01'37.165" 40.026990°	109°31'48.713" 109.530198°	40°01'37.292" 40.027026°	109°31'46.237" 109.529510°	670' FNL 494' FEL
NBU 129	40°01'23.517" 40.023199	109°31'49.572" 109.530437	40°01'23.644" 40.023234°	109°31'47.095" 109.529749°	2051' FNL 565' FEL					

RELATIVE COORDINATES - From Surface Position to Bottom Hole

WELL NAME	NORTH	EAST
NBU 921-22H4CS	-206.4'	133.2'
NBU 921-22H4BS	116.9'	137.6'
NBU 921-22H1CS	439.3'	142.0'
NBU 921-22A4CS	882.7'	136.1'
NBU 921-22A4BS	1492.1'	149.9'



BASIS OF BEARINGS IS THE EAST LINE OF THE NE 1/4 OF SECTION 22, T9S, R21E, S.L.B.&M. WHICH IS TAKEN FROM GLOBAL POSITIONING SATELLITE OBSERVATIONS TO BEAR N00°07'07"W.

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22H

WELL PAD INTERFERENCE PLAT
WELLS - NBU 921-22H4CS, NBU 921-22H4BS, NBU 921-22H1CS, NBU 921-22A4CS & NBU 921-22A4BS LOCATED IN SECTION 22, T9S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH.

609 CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 11-1-11	SURVEYED BY: W.W.	SHEET NO: 6
DATE DRAWN: 8-29-11	DRAWN BY: C.T.C.	6 OF 17
SCALE: 1" = 60'	Date Last Revised:12-02-11 C.T.C.	

RECEIVED: April 24, 2012

API Well Number: 43047526500000

PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

12" GAS LINE
6" (MAX.) LIQUID LINE

8" GAS LINE
6" (MAX.) LIQUID LINE

EXISTING ACCESS ROAD

CONSTRUCT LWC (AS NEEDED)

N05°44'16"E - 1499.60' (TO BOTTOM HOLE)

N08°46'02"E - 893.12' (TO BOTTOM HOLE)

N17°54'39"E - 461.70' (TO BOTTOM HOLE)

EXISTING METHANOL TANK

EXISTING METER/ SEPARATOR

8" GAS LINE
6" (MAX.)
LIQUID LINE

RESERVE PIT &
EXCESS CUT
STOCKPILE

RESERVE PIT
12' DEPTH
SLOPE 1.5:1

FILL CUT

DERRICK STAND

PIPETUBS

PIPERACKS

EXISTING WELL: NBU 129

NBU 921-22A4BS
NBU 921-22A4CS
NBU 921-22H1CS
NBU 921-22H4BS
NBU 921-22H4CS

N49°38'28"E - 180.58' (TO BOTTOM HOLE)

WATER TANK

SHAKER TANK

MUD TANK

MUD PUMP 1

MUD PUMP 2

GENERATOR

DIESEL TANK

BOILER

ANCHOR

ANCHOR

EXISTING WELL PAD

S32°49'59"E - 245.69' (TO BOTTOM HOLE)

CONSTRUCT DIVERSION DITCH (AS NEEDED)

TOPSOIL STOCKPILE

RESERVE PIT &
EXCESS CUT
STOCKPILE

CONSTRUCT DIVERSION DITCH (AS NEEDED)

4830

4840

WELL PAD - NBU 921-22H DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4826.9'
FINISHED GRADE ELEVATION = 4826.0'
CUT SLOPES = 1.5:1
FILL SLOPES = 1.5:1
TOTAL WELL PAD AREA = 3.36 ACRES
TOTAL DISTURBANCE AREA = 5.44 ACRES
SHRINKAGE FACTOR = 1.10
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 15,498 C.Y.
TOTAL FILL FOR WELL PAD = 1,193 C.Y.
TOPSOIL @ 6" DEPTH = 1,899 C.Y.
EXCESS MATERIAL = 14,305 C.Y.

RESERVE PIT QUANTITIES

TOTAL CUT FOR RESERVE PIT
+/- 8,870 C.Y.
RESERVE PIT CAPACITY (2' OF FREEBOARD)
+/- 33,770 BARRELS

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE

HORIZONTAL 0 30' 60' 1" = 60'
2' CONTOURS

WELL PAD - NBU 921-22H

WELL PAD - LOCATION LAYOUT
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

609 CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

SCALE: 1"=60' | DATE: 9/14/11 | SHEET NO: 7
REVISED: GRB 12/1/11 | 7 OF 17

K:\ANADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22H\NBU 921-22H.dwg, 12/2/2011 2:24:15 PM, andy

RECEIVED: April 24, 2012

API Well Number: 43047526500000

PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

12" GAS LINE
6" (MAX.) LIQUID LINE

8" GAS LINE
6" (MAX.) LIQUID LINE

EXISTING ACCESS ROAD

CONSTRUCT LWC (AS NEEDED)

4830

N05°44'16"E - 1499.60' (TO BOTTOM HOLE)

N08°46'02"E - 893.12' (TO BOTTOM HOLE)

N17°54'39"E - 461.70' (TO BOTTOM HOLE)

9 F2.6 | 10 F1.4 | 11 C4.8

45' | 23' | 8 F2.5 | 170'

EXISTING METHANOL TANK

EXISTING METER/ SEPARATOR

FILL | CUT

8" GAS LINE
6" (MAX.)
LIQUID LINE

160' | 200' | 220'

RESERVE PIT & EXCESS CUT STOCKPILE

DERRICK STAND

6 F1.9 | 7 F0.7

99' | 15'

PIPETUBS | PIPERACKS

EXISTING WELL: NBU 129

W C0.9

NBU 921-22A4BS
NBU 921-22A4CS
NBU 921-22H1CS
NBU 921-22H4BS
NBU 921-22H4CS

10' | 10' | 10' | 10'

N49°38'28"E - 180.58' (TO BOTTOM HOLE)

B | B'

C F1.0 | D F0.4 | 5 F1.2 | 1 C6.3

45'

CLOSED LOOP EQUIPMENT | SHAKER TANK | MUD TANK | MUD PUMP | TRIP TANK | GENERATOR | DIESEL TANK | BOILER

WATER TANK

ANCHOR | ANCHOR

4840

COMPLETIONS PIT
(CUTTINGS AREA)
12' DEPTH
SLOPE 1.5:1

260' | 245' | 225' | 245'

EXISTING WELL PAD

CONSTRUCT DIVERSION DITCH (AS NEEDED)

67'

S32°49'59"E - 245.69' (TO BOTTOM HOLE)

B C3.0 | A C0.7 | 3 C1.6 | 2 C5.5

80' | 15' | 162' | 170'

4 C3.3

TOPSOIL STOCKPILE

A | A'

RESERVE PIT & EXCESS CUT STOCKPILE

CONSTRUCT DIVERSION DITCH (AS NEEDED)

4830 | 4830

WELL PAD - NBU 921-22H (CLOSED LOOP) DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 4826.9'
FINISHED GRADE ELEVATION = 4826.0'
CUT SLOPES = 1.5:1
FILL SLOPES = 1.5:1
TOTAL WELL PAD AREA = 3.36 ACRES
TOTAL DISTURBANCE AREA = 5.44 ACRES
SHRINKAGE FACTOR = 1.10
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 15,498 C.Y.
TOTAL FILL FOR WELL PAD = 1,193 C.Y.
TOPSOIL @ 6" DEPTH = 1,899 C.Y.
EXCESS MATERIAL = 14,305 C.Y.

COMPLETIONS PIT QUANTITIES

TOTAL CUT FOR COMPLETIONS PIT
+/- 6,720 C.Y.
COMPLETIONS PIT CAPACITY
(2' OF FREEBOARD)
+/- 25,260 BARRELS

WELL PAD - NBU 921-22H

WELL PAD - LOCATION LAYOUT
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

609 CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078
(435) 789-1365

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE

N

HORIZONTAL 0 30' 60' 1" = 60'
2' CONTOURS

SCALE: 1"=60' | DATE: 12/1/11 | SHEET NO: 7B 7B OF 17
REVISED:

K:\ANADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22H\NBU 921-22H.dwg, 12/2/2011 2:31:11 PM, andy

RECEIVED: April 24, 2012



CROSS SECTION A-A'



CROSS SECTION B-B'

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22H

WELL PAD - CROSS SECTIONS
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

609
CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

HORIZONTAL 0 50' 100' 1" = 100'
VERTICAL 0 10' 20' 1" = 20'

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

Scale: 1"=100' | Date: 9/14/11 | SHEET NO: 8 8 OF 17
REVISED: GRB 12/1/11

K:\ANADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22HNBU 921-22H.dwg, 12/2/2011 10:40:19 AM, gettv

API Well Number: 43047526500000

PLEASE NOTE: LOCATIONS OF PROPOSED FACILITIES AND PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

12" GAS LINE
6" (MAX.) LIQUID LINE

EXISTING ACCESS ROAD

CONSTRUCT LWC (AS NEEDED)

8" GAS LINE
6" (MAX.)
LIQUID LINE

8" GAS LINE
6" (MAX.)
LIQUID LINE

FILL CUT

DISTURBANCE BOUNDARY

EXISTING WELL: NBU 129

NBU 921-22A4BS
NBU 921-22A4CS
NBU 921-22H1CS
NBU 921-22H4BS
NBU 921-22H4CS

10'

90'

RESERVE PIT

SEPARATOR/ METER HOUSE

TANKS (TYPICAL)

EXISTING WELL PAD

SEPARATOR/ METER HOUSE (15' X 30')

30'

15'

METAL CONTAINMENT

75'

DIVERSION DITCH (TO BE RECLAIMED)

PROPOSED WELL PAD

DIVERSION DITCH (TO BE RECLAIMED)

4830

4840

WELL PAD - NBU 921-22H DESIGN SUMMARY

TOTAL DISTURBANCE AREA = 5.46 ACRES (INCLUDING EXISTING)
RECLAMATION AREA = 4.31 ACRES
TOTAL WELL PAD AREA AFTER RECLAMATION = 1.15 ACRES

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE
- RECLAMATION AREA

HORIZONTAL 0 30' 60' 1" = 60'
2' CONTOURS

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22H

WELL PAD - RECLAMATION LAYOUT
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

609 CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078
(435) 789-1365

SCALE: 1"=60' | DATE: 12/1/11 | SHEET NO: 9 | 9 OF 17
REVISED:

K:\ANADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22H\NBU 921-22H.dwg, 12/2/2011 11:27:32 AM, gietty

RECEIVED: April 24, 2012

API Well Number: 43047526500000



PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: EASTERLY

PHOTO VIEW: FROM EXISTING ACCESS ROAD

CAMERA ANGLE: SOUTHWESTERLY

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22H

LOCATION PHOTOS
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH.

609 CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE (435) 789-1365
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 11-1-11	PHOTOS TAKEN BY: W.W.	SHEET NO: 10
DATE DRAWN: 8-29-11	DRAWN BY: C.T.C.	10 OF 17
Date Last Revised:11-3-11 J.G.C.		

RECEIVED: April 24, 2012

API Well Number: 43047526500000



Legend

Distance From Well Pad - NBU 921-22H To Unit Boundary: ±10,294ft

Proposed Well Location

Natural Buttes Unit Boundary

Access Route - Proposed

WELL PAD - NBU 921-22H

TOPO A
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1:100,000	NAD83 USP Central	SHEET NO: 11
DRAWN: TL	DATE: 14 Sept 2011	11 OF 17
REVISED: KGS	DATE: 4 Nov 2011	

RECEIVED: April 24, 2012



Legend

Total Proposed Road Length: ±0ft

- Well - Proposed
- Well - Existing
- Well Pad
- Road - Proposed
- Road - Existing
- County Road
- Bureau of Land Management
- Indian Reservation
- State
- Private

WELL PAD - NBU 921-22H

TOPO B
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1" = 2,000ft	NAD83 USP Central	SHEET NO: 12	
DRAWN: TL	DATE: 14 Sept 2011	12 OF 17	
REVISED: TL	DATE: 2 Dec 2011		

RECEIVED: April 24, 2012

API Well Number: 43047526500000



Well locations derived from Utah Division of Oil, Gas and Mining (UDOGM) (oilgas.ogm.utah.gov). The estimated distances from proposed bore locations to the nearest existing bore locations are based on UDOGM data.

Proposed Well	Nearest Well Bore	Footage
NBU 921-22H4CS	NBU 129	359ft
NBU 921-22H4BS	NBU 129	73ft
NBU 921-22H1CS	NBU 129	319ft
NBU 921-22A4CS	NBU 921-22A	470ft
NBU 921-22A4BS	NBU 921-22A	277ft

Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- Well - 1 Mile Radius
- Producing
- Spudded
- APD Approved
- Preliminary Location
- Deferred
- Cancelled
- Temporarily Abandoned
- Active Injector
- Location Abandoned
- Plugged & Abandoned
- Shut-In

WELL PAD - NBU 921-22H

TOPO C
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1" = 2,000ft	NAD83 USP Central	SHEET NO: 13	
DRAWN: TL	DATE: 14 Sept 2011	13 OF 17	
REVISED: TL	DATE: 2 Dec 2011		

RECEIVED: April 24, 2012



Proposed Liquid Pipeline	Length
Buried 6"(Max.) (Meter House to Edge of Pad)	±365ft
Buried 6"(Max.) (Edge of Pad to 22I Intersection)	±75ft
Buried 6"(Max.) (22I Intersection to 23C Intersection)	±545ft
Buried 6"(Max.) (23C Intersection to 22B Intersection)	±1,070ft
TOTAL PROPOSED BURIED LIQUID PIPELINE =	±2,055ft

Proposed Gas Pipeline	Length
Buried 8" (Meter House to Edge of Pad)	±365ft
Buried 8" (Edge of Pad to 22I Intersection)	±75ft
Buried 12"(22I Intersection to 23C Intersection)	±545ft
Buried 16"(23C Intersection to 22B Intersection)	±1,070ft
TOTAL PROPOSED BURIED GAS PIPELINE =	±2,055ft

Legend

Well - Proposed; Well - Existing; Well Pad; Gas Pipeline - Proposed; Gas Pipeline - To Be Upgraded; Gas Pipeline - Existing; Liquid Pipeline - Proposed; Liquid Pipeline - Existing; Road - Proposed; Road - Existing; Bureau of Land Management; Indian Reservation; State; Private

WELL PAD - NBU 921-22H

TOPO D
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1" = 2,000ft	NAD83 USP Central	SHEET NO: 14	14 OF 17
DRAWN: TL	DATE: 20 Sept 2011		
REVISED: TL	DATE: 2 Dec 2011		

RECEIVED: April 24, 2012



Proposed Liquid Pipeline	Length
Buried 6"(Max.) (Meter House to Edge of Pad)	±365ft
Buried 6"(Max.) (Edge of Pad to 22I Intersection)	±75ft
Buried 6"(Max.) (22I Intersection to 23C Intersection)	±545ft
Buried 6"(Max.) (23C Intersection to 22B Intersection)	±1,070ft
TOTAL PROPOSED BURIED LIQUID PIPELINE =	±2,055ft

Proposed Gas Pipeline	Length
Buried 8" (Meter House to Edge of Pad)	±365ft
Buried 8" (Edge of Pad to 22I Intersection)	±75ft
Buried 12"(22I Intersection to 23C Intersection)	±545ft
Buried 16"(23C Intersection to 22B Intersection)	±1,070ft
TOTAL PROPOSED BURIED GAS PIPELINE =	±2,055ft

Legend

Well - Proposed; Well - Existing; Well Pad - Proposed; Well Pad - Existing; Gas Pipeline - Proposed; Gas Pipeline - To Be Upgraded; Gas Pipeline - Existing; Liquid Pipeline - Proposed; Liquid Pipeline - Existing; Road - Proposed; Road - Existing; Bureau of Land Management; Indian Reservation; State; Private

WELL PAD - NBU 921-22H

TOPO D2 (PAD & PIPELINE DETAIL)
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1" = 500ft	NAD83 USP Central	SHEET NO: 15	15 OF 17
DRAWN: TL	DATE: 20 Sept 2011		
REVISED: TL	DATE: 2 Dec 2011		

RECEIVED: April 24, 2012

API Well Number: 43047526500000



Proposed Well	Distance To Nearest Lease Boundary
NBU 921-22H4CS	494ft
NBU 921-22H4BS	494ft
NBU 921-22H1CS	494ft
NBU 921-22A4CS	504ft
NBU 921-22A4BS	494ft

Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- Lease Boundary
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

WELL PAD - NBU 921-22H

TOPO E
NBU 921-22H4CS,
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
LOCATED IN SECTION 22, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH

Kerr-McGee Oil & Gas Onshore L.P.

1099 18th Street
Denver, Colorado 80202

609 CONSULTING, LLC
2155 North Main Street
Sheridan, Wyoming 82801
Phone 307-674-0609
Fax 307-674-0182

N

SCALE: 1" = 2,000ft	NAD83 USP Central	SHEET NO: 16	
DRAWN: TL	DATE: 14 Sept 2011	16 OF 17	
REVISED: TL	DATE: 2 Dec 2011		

RECEIVED: April 24, 2012

Kerr-McGee Oil & Gas Onshore, LP
WELL PAD – NBU 921-22H
WELLS – NBU 921-22H4CS
NBU 921-22H4BS, NBU 921-22H1CS,
NBU 921-22A4CS & NBU 921-22A4BS
Section 22, T9S, R21E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 17.7 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly direction along the Class D County Road approximately 1.8 miles to a second Class D County Road to the North. Exit right and proceed in a northerly direction along the second Class D County Road approximately 1.6 miles to a service road to the southeast. Exit right and proceed in a southeasterly direction along the service road approximately 0.4 miles to a second service road to the south. Exit left and proceed in a southeasterly direction along the second service road approximately 105 feet to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 45.0 miles in a southerly direction.

RECEIVED: April 24, 2012

API Well Number: 43047526500000

Scientific Drilling
Rocky Mountain Operations

Project: Uintah County, UT UTM12
Site: NBU 921-22H PAD
Well: NBU 921-22H1CS
Wellbore: OH
Design: PLAN #1 PRELIMINARY

Anadarko Petroleum Corporation

WELL DETAILS: NBU 921-22H1CS

GL 4826 & KB 4 @ 4830.00ft (ASSUMED)

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14537772.47	2051971.43	40° 1' 22.379 N	109° 31' 48.018 W

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
BLACKHAWK - plan hits target center	10443.00	439.23	141.69	14538213.98	2052105.85	40° 1' 26.720 N	109° 31' 46.196 W	Circle (Radius: 25.00)
PBHL - plan hits target center	11043.00	439.23	141.69	14538213.98	2052105.85	40° 1' 26.720 N	109° 31' 46.196 W	Circle (Radius: 100.00)



Azimuths to True North
Magnetic North: 11.03°

Magnetic Field
Strength: 52291.1snT
Dip Angle: 65.87°
Date: 2011/12/06
Model: IGRF2010





SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	
787.50	9.75	17.88	785.15	39.38	12.70	2.00	17.88	41.38	
2989.17	9.75	17.88	2955.02	394.23	127.17	0.00	0.00	414.23	
3546.31	0.00	0.00	3509.48	439.23	141.69	1.75	180.00	461.52	
11079.84	0.00	0.00	11043.00	439.23	141.69	0.00	0.00	461.52	PBHL_NBU 921-22H1CS

PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsoid: Clarke 1866
Zone: Zone 12N (114 W to 108 W)
Location: SECTION 22 T9S R21E
System Datum: Mean Sea Level

FORMATION TOP DETAILS

TVDPath	MDPath	Formation
1532.00	1545.29	GREEN RIVER
1862.00	1880.13	BIRDSNEST
2368.00	2393.55	MAHOGANY
4894.00	4930.84	WASATCH
7786.00	7822.84	MESAVERDE
10003.00	10039.84	SEGO
10062.00	10098.84	CASTLEGATE
10443.00	10479.84	BLACKHAWK

CASING DETAILS

TVD	MD	Name	Size
2818.00	2850.14	8 5/8"	8.625

Plan: PLAN #1 PRELIMINARY (NBU 921-22H1CS/OH)

Created By: RobertScott Date: 15:55, December 06 2011

API Well Number: 43047526500000

Scientific Drilling
Rocky Mountain Operations

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12
NBU 921-22H PAD
NBU 921-22H1CS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

06 December, 2011

Anadarko Petroleum Corporation

RECEIVED: April 27, 2012

Scientific Drilling
Rocky Mountain Operations

SDI
Planning Report

Anadarko Petroleum Corporation

Database:	EDM5000-RobertS-Local	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Company:	Kerr McGee Oil and Gas Onshore LP	**TVD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	**MD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Site:	NBU 921-22H PAD	**North Reference:**	True
Well:	NBU 921-22H1CS	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Project Uintah County, UT UTM12

Map System:	Universal Transverse Mercator (US Survey Feet)	**System Datum:**	Mean Sea Level
Geo Datum:	NAD 1927 - Western US		
Map Zone:	Zone 12N (114 W to 108 W)		

Site NBU 921-22H PAD, SECTION 22 T9S R21E

Site Position:		**Northing:**	14,537,789.43 usft	**Latitude:**	40° 1' 22.548 N
From:	Lat/Long	**Easting:**	2,051,961.07 usft	**Longitude:**	109° 31' 48.148 W
Position Uncertainty:	0.00 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	0.95 °

Well NBU 921-22H1CS, 2179 FNL 637 FEL

Well Position	**+N/-S**	-17.12 ft	**Northing:**	14,537,772.48 usft	**Latitude:**	40° 1' 22.379 N
	+E/-W	10.08 ft	**Easting:**	2,051,971.43 usft	**Longitude:**	109° 31' 48.018 W
Position Uncertainty		0.00 ft	**Wellhead Elevation:**		**Ground Level:**	4,826.00 ft

Wellbore OH

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2011/12/06	11.03	65.87	52,291

Design PLAN #1 PRELIMINARY

Audit Notes:

Version:		**Phase:**	PLAN	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	17.88

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
787.50	9.75	17.88	785.15	39.38	12.70	2.00	2.00	0.00	17.88	
2,989.17	9.75	17.88	2,955.02	394.23	127.17	0.00	0.00	0.00	0.00	
3,546.31	0.00	0.00	3,509.48	439.23	141.69	1.75	-1.75	0.00	180.00	
11,079.84	0.00	0.00	11,043.00	439.23	141.69	0.00	0.00	0.00	0.00	PBHL_NBU 921-22H

RECEIVED: April 27, 2012

Scientific Drilling
Rocky Mountain Operations

SDI
Planning Report

Anadarko Petroleum Corporation

Database:	EDM5000-RobertS-Local	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Company:	Kerr McGee Oil and Gas Onshore LP	**TVD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	**MD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Site:	NBU 921-22H PAD	**North Reference:**	True
Well:	NBU 921-22H1CS	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2.00									
400.00	2.00	17.88	399.98	1.66	0.54	1.75	2.00	2.00	0.00
500.00	4.00	17.88	499.84	6.64	2.14	6.98	2.00	2.00	0.00
600.00	6.00	17.88	599.45	14.94	4.82	15.69	2.00	2.00	0.00
700.00	8.00	17.88	698.70	26.53	8.56	27.88	2.00	2.00	0.00
787.50	9.75	17.88	785.15	39.38	12.70	41.38	2.00	2.00	0.00
Start 2201.67 hold at 787.50 MD									
800.00	9.75	17.88	797.47	41.40	13.35	43.50	0.00	0.00	0.00
900.00	9.75	17.88	896.03	57.51	18.55	60.43	0.00	0.00	0.00
1,000.00	9.75	17.88	994.58	73.63	23.75	77.37	0.00	0.00	0.00
1,100.00	9.75	17.88	1,093.14	89.75	28.95	94.30	0.00	0.00	0.00
1,200.00	9.75	17.88	1,191.69	105.86	34.15	111.24	0.00	0.00	0.00
1,300.00	9.75	17.88	1,290.25	121.98	39.35	128.17	0.00	0.00	0.00
1,400.00	9.75	17.88	1,388.80	138.10	44.55	145.11	0.00	0.00	0.00
1,500.00	9.75	17.88	1,487.36	154.22	49.75	162.04	0.00	0.00	0.00
1,545.29	9.75	17.88	1,532.00	161.52	52.10	169.71	0.00	0.00	0.00
GREEN RIVER									
1,600.00	9.75	17.88	1,585.91	170.33	54.95	178.98	0.00	0.00	0.00
1,700.00	9.75	17.88	1,684.47	186.45	60.14	195.91	0.00	0.00	0.00
1,800.00	9.75	17.88	1,783.03	202.57	65.34	212.85	0.00	0.00	0.00
1,880.13	9.75	17.88	1,862.00	215.48	69.51	226.42	0.00	0.00	0.00
BIRDSNEST									
1,900.00	9.75	17.88	1,881.58	218.68	70.54	229.78	0.00	0.00	0.00
2,000.00	9.75	17.88	1,980.14	234.80	75.74	246.72	0.00	0.00	0.00
2,100.00	9.75	17.88	2,078.69	250.92	80.94	263.65	0.00	0.00	0.00
2,200.00	9.75	17.88	2,177.25	267.04	86.14	280.59	0.00	0.00	0.00
2,300.00	9.75	17.88	2,275.80	283.15	91.34	297.52	0.00	0.00	0.00
2,393.55	9.75	17.88	2,368.00	298.23	96.20	313.36	0.00	0.00	0.00
MAHOGANY									
2,400.00	9.75	17.88	2,374.36	299.27	96.54	314.45	0.00	0.00	0.00
2,500.00	9.75	17.88	2,472.92	315.39	101.74	331.39	0.00	0.00	0.00
2,600.00	9.75	17.88	2,571.47	331.50	106.94	348.32	0.00	0.00	0.00
2,700.00	9.75	17.88	2,670.03	347.62	112.14	365.26	0.00	0.00	0.00
2,800.00	9.75	17.88	2,768.58	363.74	117.33	382.19	0.00	0.00	0.00
2,850.14	9.75	17.88	2,818.00	371.82	119.94	390.69	0.00	0.00	0.00
8 5/8"									
2,900.00	9.75	17.88	2,867.14	379.86	122.53	399.13	0.00	0.00	0.00
2,989.17	9.75	17.88	2,955.02	394.23	127.17	414.23	0.00	0.00	0.00
Start Drop -1.75									
3,000.00	9.56	17.88	2,965.70	395.96	127.73	416.05	1.75	-1.75	0.00
3,100.00	7.81	17.88	3,064.55	410.33	132.36	431.15	1.75	-1.75	0.00
3,200.00	6.06	17.88	3,163.81	421.82	136.07	443.22	1.75	-1.75	0.00
3,300.00	4.31	17.88	3,263.40	430.42	138.84	452.26	1.75	-1.75	0.00
3,400.00	2.56	17.88	3,363.21	436.12	140.68	458.25	1.75	-1.75	0.00
3,500.00	0.81	17.88	3,463.17	438.92	141.59	461.19	1.75	-1.75	0.00
3,546.31	0.00	0.00	3,509.48	439.23	141.69	461.52	1.75	-1.75	0.00
Start 7533.52 hold at 3546.31 MD									
3,600.00	0.00	0.00	3,563.16	439.23	141.69	461.52	0.00	0.00	0.00
3,700.00	0.00	0.00	3,663.16	439.23	141.69	461.52	0.00	0.00	0.00

Scientific Drilling
Rocky Mountain Operations

SDI
Planning Report

Anadarko Petroleum Corporation

Database:	EDM5000-RobertS-Local	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Company:	Kerr McGee Oil and Gas Onshore LP	**TVD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	**MD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Site:	NBU 921-22H PAD	**North Reference:**	True
Well:	NBU 921-22H1CS	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,800.00	0.00	0.00	3,763.16	439.23	141.69	461.52	0.00	0.00	0.00
3,900.00	0.00	0.00	3,863.16	439.23	141.69	461.52	0.00	0.00	0.00
4,000.00	0.00	0.00	3,963.16	439.23	141.69	461.52	0.00	0.00	0.00
4,100.00	0.00	0.00	4,063.16	439.23	141.69	461.52	0.00	0.00	0.00
4,200.00	0.00	0.00	4,163.16	439.23	141.69	461.52	0.00	0.00	0.00
4,300.00	0.00	0.00	4,263.16	439.23	141.69	461.52	0.00	0.00	0.00
4,400.00	0.00	0.00	4,363.16	439.23	141.69	461.52	0.00	0.00	0.00
4,500.00	0.00	0.00	4,463.16	439.23	141.69	461.52	0.00	0.00	0.00
4,600.00	0.00	0.00	4,563.16	439.23	141.69	461.52	0.00	0.00	0.00
4,700.00	0.00	0.00	4,663.16	439.23	141.69	461.52	0.00	0.00	0.00
4,800.00	0.00	0.00	4,763.16	439.23	141.69	461.52	0.00	0.00	0.00
4,900.00	0.00	0.00	4,863.16	439.23	141.69	461.52	0.00	0.00	0.00
4,930.84	0.00	0.00	4,894.00	439.23	141.69	461.52	0.00	0.00	0.00
WASATCH									
5,000.00	0.00	0.00	4,963.16	439.23	141.69	461.52	0.00	0.00	0.00
5,100.00	0.00	0.00	5,063.16	439.23	141.69	461.52	0.00	0.00	0.00
5,200.00	0.00	0.00	5,163.16	439.23	141.69	461.52	0.00	0.00	0.00
5,300.00	0.00	0.00	5,263.16	439.23	141.69	461.52	0.00	0.00	0.00
5,400.00	0.00	0.00	5,363.16	439.23	141.69	461.52	0.00	0.00	0.00
5,500.00	0.00	0.00	5,463.16	439.23	141.69	461.52	0.00	0.00	0.00
5,600.00	0.00	0.00	5,563.16	439.23	141.69	461.52	0.00	0.00	0.00
5,700.00	0.00	0.00	5,663.16	439.23	141.69	461.52	0.00	0.00	0.00
5,800.00	0.00	0.00	5,763.16	439.23	141.69	461.52	0.00	0.00	0.00
5,900.00	0.00	0.00	5,863.16	439.23	141.69	461.52	0.00	0.00	0.00
6,000.00	0.00	0.00	5,963.16	439.23	141.69	461.52	0.00	0.00	0.00
6,100.00	0.00	0.00	6,063.16	439.23	141.69	461.52	0.00	0.00	0.00
6,200.00	0.00	0.00	6,163.16	439.23	141.69	461.52	0.00	0.00	0.00
6,300.00	0.00	0.00	6,263.16	439.23	141.69	461.52	0.00	0.00	0.00
6,400.00	0.00	0.00	6,363.16	439.23	141.69	461.52	0.00	0.00	0.00
6,500.00	0.00	0.00	6,463.16	439.23	141.69	461.52	0.00	0.00	0.00
6,600.00	0.00	0.00	6,563.16	439.23	141.69	461.52	0.00	0.00	0.00
6,700.00	0.00	0.00	6,663.16	439.23	141.69	461.52	0.00	0.00	0.00
6,800.00	0.00	0.00	6,763.16	439.23	141.69	461.52	0.00	0.00	0.00
6,900.00	0.00	0.00	6,863.16	439.23	141.69	461.52	0.00	0.00	0.00
7,000.00	0.00	0.00	6,963.16	439.23	141.69	461.52	0.00	0.00	0.00
7,100.00	0.00	0.00	7,063.16	439.23	141.69	461.52	0.00	0.00	0.00
7,200.00	0.00	0.00	7,163.16	439.23	141.69	461.52	0.00	0.00	0.00
7,300.00	0.00	0.00	7,263.16	439.23	141.69	461.52	0.00	0.00	0.00
7,400.00	0.00	0.00	7,363.16	439.23	141.69	461.52	0.00	0.00	0.00
7,500.00	0.00	0.00	7,463.16	439.23	141.69	461.52	0.00	0.00	0.00
7,600.00	0.00	0.00	7,563.16	439.23	141.69	461.52	0.00	0.00	0.00
7,700.00	0.00	0.00	7,663.16	439.23	141.69	461.52	0.00	0.00	0.00
7,800.00	0.00	0.00	7,763.16	439.23	141.69	461.52	0.00	0.00	0.00
7,822.84	0.00	0.00	7,786.00	439.23	141.69	461.52	0.00	0.00	0.00
MESAVERDE									
7,900.00	0.00	0.00	7,863.16	439.23	141.69	461.52	0.00	0.00	0.00
8,000.00	0.00	0.00	7,963.16	439.23	141.69	461.52	0.00	0.00	0.00
8,100.00	0.00	0.00	8,063.16	439.23	141.69	461.52	0.00	0.00	0.00
8,200.00	0.00	0.00	8,163.16	439.23	141.69	461.52	0.00	0.00	0.00
8,300.00	0.00	0.00	8,263.16	439.23	141.69	461.52	0.00	0.00	0.00
8,400.00	0.00	0.00	8,363.16	439.23	141.69	461.52	0.00	0.00	0.00
8,500.00	0.00	0.00	8,463.16	439.23	141.69	461.52	0.00	0.00	0.00
8,600.00	0.00	0.00	8,563.16	439.23	141.69	461.52	0.00	0.00	0.00
8,700.00	0.00	0.00	8,663.16	439.23	141.69	461.52	0.00	0.00	0.00

Scientific Drilling
Rocky Mountain Operations

SDI
Planning Report

Anadarko Petroleum Corporation

Database:	EDM5000-RobertS-Local	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Company:	Kerr McGee Oil and Gas Onshore LP	**TVD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	**MD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Site:	NBU 921-22H PAD	**North Reference:**	True
Well:	NBU 921-22H1CS	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,800.00	0.00	0.00	8,763.16	439.23	141.69	461.52	0.00	0.00	0.00
8,900.00	0.00	0.00	8,863.16	439.23	141.69	461.52	0.00	0.00	0.00
9,000.00	0.00	0.00	8,963.16	439.23	141.69	461.52	0.00	0.00	0.00
9,100.00	0.00	0.00	9,063.16	439.23	141.69	461.52	0.00	0.00	0.00
9,200.00	0.00	0.00	9,163.16	439.23	141.69	461.52	0.00	0.00	0.00
9,300.00	0.00	0.00	9,263.16	439.23	141.69	461.52	0.00	0.00	0.00
9,400.00	0.00	0.00	9,363.16	439.23	141.69	461.52	0.00	0.00	0.00
9,500.00	0.00	0.00	9,463.16	439.23	141.69	461.52	0.00	0.00	0.00
9,600.00	0.00	0.00	9,563.16	439.23	141.69	461.52	0.00	0.00	0.00
9,700.00	0.00	0.00	9,663.16	439.23	141.69	461.52	0.00	0.00	0.00
9,800.00	0.00	0.00	9,763.16	439.23	141.69	461.52	0.00	0.00	0.00
9,900.00	0.00	0.00	9,863.16	439.23	141.69	461.52	0.00	0.00	0.00
10,000.00	0.00	0.00	9,963.16	439.23	141.69	461.52	0.00	0.00	0.00
10,039.84	0.00	0.00	10,003.00	439.23	141.69	461.52	0.00	0.00	0.00
SEGO									
10,098.84	0.00	0.00	10,062.00	439.23	141.69	461.52	0.00	0.00	0.00
CASTLEGATE									
10,100.00	0.00	0.00	10,063.16	439.23	141.69	461.52	0.00	0.00	0.00
10,200.00	0.00	0.00	10,163.16	439.23	141.69	461.52	0.00	0.00	0.00
10,300.00	0.00	0.00	10,263.16	439.23	141.69	461.52	0.00	0.00	0.00
10,400.00	0.00	0.00	10,363.16	439.23	141.69	461.52	0.00	0.00	0.00
10,479.84	0.00	0.00	10,443.00	439.23	141.69	461.52	0.00	0.00	0.00
BLACKHAWK - BLACKHAWK_NBU 921-22H1CS									
10,500.00	0.00	0.00	10,463.16	439.23	141.69	461.52	0.00	0.00	0.00
10,600.00	0.00	0.00	10,563.16	439.23	141.69	461.52	0.00	0.00	0.00
10,700.00	0.00	0.00	10,663.16	439.23	141.69	461.52	0.00	0.00	0.00
10,800.00	0.00	0.00	10,763.16	439.23	141.69	461.52	0.00	0.00	0.00
10,900.00	0.00	0.00	10,863.16	439.23	141.69	461.52	0.00	0.00	0.00
11,000.00	0.00	0.00	10,963.16	439.23	141.69	461.52	0.00	0.00	0.00
11,079.84	0.00	0.00	11,043.00	439.23	141.69	461.52	0.00	0.00	0.00
TD at 11079.84 - PBHL_NBU 921-22H1CS									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BLACKHAWK_NBU 921 - plan hits target center - Circle (radius 25.00)	0.00	0.00	10,443.00	439.23	141.69	14,538,213.99	2,052,105.85	40° 1' 26.720 N	109° 31' 46.196 W
PBHL_NBU 921-22H1C - plan hits target center - Circle (radius 100.00)	0.00	0.00	11,043.00	439.23	141.69	14,538,213.99	2,052,105.85	40° 1' 26.720 N	109° 31' 46.196 W

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
2,850.14	2,818.00	8 5/8"	8.625	11.000

Scientific Drilling
Rocky Mountain Operations

SDI
Planning Report

Anadarko Petroleum Corporation

Database:	EDM5000-RobertS-Local	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Company:	Kerr McGee Oil and Gas Onshore LP	**TVD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	**MD Reference:**	GL 4826 & KB 4 @ 4830.00ft (ASSUMED)
Site:	NBU 921-22H PAD	**North Reference:**	True
Well:	NBU 921-22H1CS	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,545.29	1,532.00	GREEN RIVER			
1,880.13	1,862.00	BIRDSNEST			
2,393.55	2,368.00	MAHOGANY			
4,930.84	4,894.00	WASATCH			
7,822.84	7,786.00	MESAVERDE			
10,039.84	10,003.00	SEGO			
10,098.84	10,062.00	CASTLEGATE			
10,479.84	10,443.00	BLACKHAWK			

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
787.50	785.15	39.38	12.70	Start 2201.67 hold at 787.50 MD
2,989.17	2,955.02	394.23	127.17	Start Drop -1.75
3,546.31	3,509.48	439.23	141.69	Start 7533.52 hold at 3546.31 MD
11,079.84	11,043.00	439.23	141.69	TD at 11079.84

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 921-22H Pad

API #		**NBU 921-22A4BS**		
	Surface:	2162 FNL / 647 FEL	SENE	Lot
	BHL:	670 FNL / 494 FEL	NENE	Lot
API #		**NBU 921-22A4CS**		
	Surface:	2170 FNL / 642 FEL	SENE	Lot
	BHL:	1288 FNL / 504 FEL	SENE	Lot
API #		**NBU 921-22H1CS**		
	Surface:	2179 FNL / 637 FEL	SENE	Lot
	BHL:	1740 FNL / 494 FEL	SENE	Lot
API #		**NBU 921-22H4BS**		
	Surface:	2188 FNL / 632 FEL	SENE	Lot
	BHL:	2071 FNL / 494 FEL	SENE	Lot
API #		**NBU 921-22H4CS**		
	Surface:	2196 FNL / 627 FEL	SENE	Lot
	BHL:	2403 FNL / 494 FEL	SENE	Lot

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on October 3-4, 2011. Present were:

·
- Bucky Secakuku (10/4/2011 only) - BIA;
- LeAllen Blackhair, Rainey Longhair - Ute Indian Tribe;
- Kelly Jo Jackson - Montgomery Archeological Consultants Inc.;
- Scott Carson - Smiling Lake Consulting;
- John Slaugh, Mitch Batty - Timberline Engineering & Land Surveying, Inc.;
- Laura Abrams, Charles Chase, Raleen White, Doyle Holmes, Lovel Young, Sheila Wopsock - Kerr-McGee

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with Onshore Order #1, Kerr-McGee will, in accordance with BMPs, improve or maintain existing roads in a condition that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing will be performed where excessive rutting or erosion may occur. Dust control will be performed as necessary to ensure safe operating conditions.

RECEIVED: April 24, 2012

Roads, gathering lines and electrical distribution lines will occupy common disturbance corridors where possible. Where available, roadways will be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor will overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Please refer to Topo B, for existing roads.

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BIA.

Each new well pad or pad expansion may require construction of a new access road and/or de-commissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, as per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met. As applicable, Kerr-McGee may use unimproved and/or two-track roads for lease operations, to lessen total disturbance.

Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities, such as V- or wing-ditches, will be constructed to divert surface water runoff. Drainage features, including culverts, will be constructed or installed prior to commencing other operations, including drilling or facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s), as necessary.

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activity will not be conducted using frozen or saturated materials or during periods when significant watershed damage (e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating conditions. All vehicular traffic, personnel movement, construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

No new access road is proposed for this well pad - See Topo B.

RECEIVED: April 24, 2012

C. Location of Existing Wells:

A) Refer to Topo Map C.

D. Location of Existing and/or Proposed Facilities:

This pad will expand the existing pad for the NBU 129, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on December 19, 2011. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad. A berm will be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will generally be constructed of compacted subsoil or corrugated metal, and will hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite (typically Shadow Gray). A production facility layout is provided as part of a project-specific APD, ROW or NOS submission.

GAS GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The gas gathering pipeline material: Steel line pipe. Surface = Bare pipe. Buried = Coated with fusion bonded epoxy coating (or equivalent). The total gas gathering pipeline distance from the meter to the tie in point is ±2,055' and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±2,055' (0.39 miles) – Section 22 T9S R21E (NE/4) – On-lease UTU 010950-A Ute Indian Tribe surface, New 8", 12" and 16" buried gas gathering pipeline from the meter to the NBU 921-22B intersection. Please refer to Topo D2 - Pad and Pipeline Detail.

LIQUID GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The total liquid gathering pipeline distance from the separator to the tie in point is ±2,055' and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±2,055' (0.39 miles) – Section 22 T9S R21E (NE/4) – On-lease UTU 010950-A Ute Indian Tribe surface, New 6" buried liquid gathering pipeline from the meter to the NBU 921-22B intersection. Please refer to Topo D2 - Pad and Pipeline Detail.

Pipeline Gathering Construction

Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee. Gas gathering pipeline(s,) gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. The area of disturbance during construction from the edge of road or well pad will typically be 30' in width. Where pipelines run cross country, the width of disturbance will typically be 45 ft for buried lines and 30 ft for surface lines. In addition, Kerr-McGee requests for a permanent 30' disturbance width that will be maintained for the portion adjacent to the road. The need for the 30' permanent disturbance width is for maintenance and repairs. Cross country permanent disturbance width also are required to be 30ft.

RECEIVED: April 24, 2012

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. In some surface pipeline installation instances pipe cannot be constructed where it will lay. In these cases where an above-ground pipeline is constructed parallel and adjacent to a road, it will be welded/fused on the road and then lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment.

Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2 inches (typically fuel gas lines) to 24 inches (typically transportation lines) in diameter, but 6 to 16 inches is typical for a buried gas line. The diameter of liquids pipelines may vary from 2 inches to 12 inches, but 6 inches is the typical diameter. Gas lift lines may vary from 2 to 12 inches in diameter, but 6-inch diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

Typically, to install a buried pipeline, topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6 feet, but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18-48 inches.

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route’s intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, Kerr-McGee will apply all applicable Army Corps mandates as well as the BLM’s Hydraulic Considerations for Pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface.

Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.
When no longer deemed necessary by the operator, Kerr-McGee or it's successor will consult with the Vernal BIA Office before terminating of the use of the pipeline(s).

RECEIVED: April 24, 2012

The Anadarko Completions Transportation System (ACTS) information:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit is lined and will be used for the wells drilled on the pad or used as part of our Anadarko Completions Transportation (ACTS) system which is discussed in more detail below. Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If Kerr-McGee does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit will be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The pit will be refurbished as follows when a traditional drill pit is used: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit.

All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit .

ACTS will require temporarily laying multiple 6” aluminum water transfer lines on the surface between either existing or refurbished reserve pits. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The temporary ACTS lines will be permitted under a separate cover to the Ute Indian Tribe.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. Kerr-McGee requests to keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. Kerr-McGee understands that due to the temporary nature of this system, BIA considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BIA.

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources:

Permit # 49-2307	JD Field Services	Green River- Section 15, T2N, R22E
Permit # 49-2321	R.N. Industries	White River- Section 2, T10S, R24E
Permit # 49-2319	R.N. Industries	White River- Various Sources
Permit # 49-2320	R.N. Industries	Green River- Section 33, T8S, R23E

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

RECEIVED: April 24, 2012

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from Tribal lands without prior approval from the BIA. A source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BIA.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. Kerr-McGee also maintains a Spill Control and Countermeasure Plan, which includes notification requirements, including the BIA, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of CERCLA, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, Kerr-McGee will comply with the notification requirements of NTL-3A. Drill cuttings and/or drilling fluids will be contained in the reserve/frac pit whether a closed loop system is used or not. Cuttings will be buried in pit(s) upon closure. Unless specifically approved by the BIA, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc.). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/ sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by the BIA. Should timely removal not be feasible, the pit will be netted as soon as practical. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with an impermeable liner. The liner will be a synthetic material 30 mil or thicker. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions (freeboard, etc.) allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per Onshore Order Number 7 (OSO 7). Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Otherwise, fluids disposal locations and associated haul routes, for ROW consideration, are typically depicted on Topo A of individual projects. Revisions to the water source or method of transportation will be subject to written approval from the BIA.

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

RECEIVED: April 24, 2012

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term “hazardous materials” as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. Kerr-McGee maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time. Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

RECEIVED: April 24, 2012

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E
NBU #159 in Sec. 35 T9S R21E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E
CIGE 112D SWD in Sec. 19 T9S R21E
CIGE 114 SWD in Sec. 34 T9S R21E
NBU 921-34K SWD in Sec. 34 T9S R21E
NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

No additional ancillary facilities are planned for this location.

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits.

For the protection of livestock and wildlife, all open pits and cellars will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/ Produced Liquid tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BIA.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

RECEIVED: April 24, 2012

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BIA for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left “rough” after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by Kerr-McGee. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BIA will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site to the approximate contour that existed prior to pad construction, final grading will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers, where practical. The surface soil material will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep, where practical. The entire area will be uniformly covered with the depressions constructed perpendicular to the natural flow of water.

Reclamation of roads will be performed at the discretion of the BIA/Tribe. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications as proposed below in "Measures Common to Interim and Final Reclamation".

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BIA/Tribe.

Measures Common to Interim and Final Reclamation

Soil preparation will be conducted using a disk for areas in need of more soil preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

RECEIVED: April 24, 2012

Seeding will occur year-round as conditions allow and will typically be accomplished through the use of a no-till rangeland style seed drill with a "picker box" in order to seed "fluffy" seed. Where drill seeding is not the preferred method, seed will be broadcast and then raked into the ground at double the rate of drill seeding. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for

re-vegetation. The seed mixes will be selected from a list provided by or approved by the BIA/Tribe or a specific seed mix will be proposed by Kerr-McGee to the BIA/Tribe and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be maintained by Kerr-McGee. Every effort will be made to obtain "cheat grass free seed".

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Indian Ricegrass (Nezpar)	3
Sandberg Bluegrass	0.75
Bottlebrush Squirreltail	1
Great Basin Wildrye	0.5
Crested Wheatgrass	1.5
Winterfat	0.25
Shadscale	1.5
Four-wing Saltbrush	0.75
Forage Kochia	0.25
Total	9.5

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Weed Control

Noxious weeds will be controlled in akk orihect areas un accordance with all applicable rules and regulations.

K. Surface/Mineral Ownership:

Ute Indian Tribe
P.O. Box 70
988 South 7500 East Annex Building
Fort Duschesne, UT 84026
(435) 722-4307

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435)781-4400

L. Other Information:

Onsite Specifics:

- Double-lined pit
- Arch monitor during construction

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and Kerr-McGee will provide immediate notification to the BIA.

Resource Reports:

A Class I literature survey was completed in December, 2011 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 11-406.

A paleontological reconnaissance survey was completed on November 17, 2011 by SWCA Environmental Consultants. For additional details please refer to report UT11-14314-117A.

Biological field survey was completed on August 8, 2011 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-568.

Proposed Action Annual Emissions Tables:

Table 1: Proposed Action Annual Emissions (tons/year)[1]

Pollutant	Development	Production	Total
NOx	3.8	0.12	3.92
CO	2.2	0.11	2.31
VOC	0.1	4.9	5
SO_2	0.005	0.0043	0.0093
PM_{10}	1.7	0.11	1.81
$PM_{2.5}$	0.4	0.025	0.425
Benzene	2.2E-03	0.044	0.046
Toluene	1.6E-03	0.103	0.105
Ethylbenzene	3.4E-04	0.005	0.005
Xylene	1.1E-03	0.076	0.077
n-Hexane	1.7E-04	0.145	0.145
Formaldehyde	1.3E-02	8.64E-05	1.31E-02

[1] Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison

Species	Proposed Action Production Emissions (ton/yr)	2012 Uintah Basin Emission Inventory[a] (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	19.6	16,547	0.12%
VOC	25	127,495	0.02%

[a] http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html Uintah Basin Data

M. Lessee's or Operators' Representative & Certification:

Laura Abrams
Regulatory Analyst II
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6356

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Laura Abrams

Decenber 19, 2011
Date

Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779

October 10, 2011

Ms. Diana Mason
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11
NBU 921-22H1CS
T9S-R21E
Section 22 SENE (Surface and Bottom Hole)
Surface: 2179' FNL, 637' FEL
Bottom Hole: 1740' FNL, 494' FEL
Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling.

- Kerr-McGee's NBU 921-22H1CS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing roads and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.

Therefore, based on the above stated information, Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joe Matney

Joe Matney
Sr. Staff Landman

RECEIVED: April 24, 2012

API Well Number: 43047526500000



API Number: 4304752650

Well Name: NBU 921-22H1CS

Township T0.9 . Range R2.1 . Section 22

Meridian: SLBM

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:
Map Produced by Diana Mason

Units
STATUS
- ACTIVE
- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Fields
STATUS
- Unknown
- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- STORAGE
- TERMINATED

Wells Query
Status
- APD - Aproved Permit
- DRL - Spuded (Drilling Commenced)
- GIW - Gas Injection
- GS - Gas Storage
- LA - Location Abandoned
- LOC - New Location
- OPS - Operation Suspended
- PA - Plugged Abandoned
- PGW - Producing Gas Well
- POW - Producing Oil Well
- RET - Returned APD
- SGW - Shut-in Gas Well
- SOW - Shut-in Oil Well
- TA - Temp. Abandoned
- TW - Test Well
- WDW - Water Disposal
- WIW - Water Injection Well
- WSW - Water Supply Well

1,500 750 0 1,500 Feet

1:14,184

RECEIVED: May 11, 2012

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

May 14, 2012

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2012 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
WELL PAD - NBU 921-22K		
43-047-52550	NBU 921-22K2AS	Sec 22 T09S R21E 1748 FSL 1611 FWL
		BHL Sec 22 T09S R21E 2366 FSL 1832 FWL
43-047-52551	NBU 921-22K4CS	Sec 22 T09S R21E 1753 FSL 1640 FWL
		BHL Sec 22 T09S R21E 1576 FSL 2147 FWL
43-047-52552	NBU 921-22N1BS	Sec 22 T09S R21E 1751 FSL 1630 FWL
		BHL Sec 22 T09S R21E 1244 FSL 2147 FWL
43-047-52575	NBU 921-22F4CS	Sec 22 T09S R21E 1755 FSL 1650 FWL
		BHL Sec 22 T09S R21E 2406 FNL 2148 FWL
43-047-52576	NBU 921-22F3DS	Sec 22 T09S R21E 1747 FSL 1601 FWL
		BHL Sec 22 T09S R21E 2634 FNL 1870 FWL
43-047-52580	NBU 921-22N1CS	Sec 22 T09S R21E 1750 FSL 1620 FWL
		BHL Sec 22 T09S R21E 0912 FSL 2146 FWL
WELL PAD - NBU 921-22B		
43-047-52553	NBU 921-22G1CS	Sec 22 T09S R21E 0973 FNL 1861 FEL
		BHL Sec 22 T09S R21E 1574 FNL 1818 FEL
43-047-52554	NBU 921-22B4CS	Sec 22 T09S R21E 0965 FNL 1854 FEL
		BHL Sec 22 T09S R21E 1243 FNL 1819 FEL
43-047-52555	NBU 921-22B4BS	Sec 22 T09S R21E 0935 FNL 1828 FEL
		BHL Sec 22 T09S R21E 0911 FNL 1819 FEL
43-047-52556	NBU 921-22B1CS	Sec 22 T09S R21E 0950 FNL 1841 FEL
		BHL Sec 22 T09S R21E 0579 FNL 1819 FEL

RECEIVED: May 15, 2012

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-52557	NBU 921-22B1BS	Sec 22 T09S R21E 0958 FNL 1848 FEL
		BHL Sec 22 T09S R21E 0249 FNL 1819 FEL
43-047-52607	NBU 921-22A1S	Sec 22 T09S R21E 0943 FNL 1835 FEL
		BHL Sec 22 T09S R21E 0386 FNL 0464 FEL
WELL PAD - NBU 921-22C		
43-047-52558	NBU 921-22C1BS	Sec 22 T09S R21E 0691 FNL 2010 FWL
		BHL Sec 22 T09S R21E 0085 FNL 2150 FWL
43-047-52567	NBU 921-22C4CS	Sec 22 T09S R21E 0696 FNL 2001 FWL
		BHL Sec 22 T09S R21E 1078 FNL 2149 FWL
43-047-52569	NBU 921-22F1BS	Sec 22 T09S R21E 0701 FNL 1993 FWL
		BHL Sec 22 T09S R21E 1410 FNL 2149 FWL
43-047-52570	NBU 921-22F1CS	Sec 22 T09S R21E 0707 FNL 1984 FWL
		BHL Sec 22 T09S R21E 1742 FNL 2149 FWL
43-047-52571	NBU 921-22F4BS	Sec 22 T09S R21E 0712 FNL 1976 FWL
		BHL Sec 22 T09S R21E 2073 FNL 2149 FWL
WELL PAD - NBU 921-22I		
43-047-52560	NBU 921-22I1CS	Sec 22 T09S R21E 1973 FSL 0620 FEL
		BHL Sec 22 T09S R21E 2237 FSL 0494 FEL
43-047-52561	NBU 921-22I1BS	Sec 22 T09S R21E 1981 FSL 0626 FEL
		BHL Sec 22 T09S R21E 2569 FSL 0494 FEL
43-047-52562	NBU 921-22G4CS	Sec 22 T09S R21E 2013 FSL 0650 FEL
		BHL Sec 22 T09S R21E 2569 FNL 1818 FEL
43-047-52564	NBU 921-22J4CS	Sec 22 T09S R21E 1989 FSL 0632 FEL
		BHL Sec 22 T09S R21E 1410 FSL 1817 FEL
43-047-52565	NBU 921-22J4AS	Sec 22 T09S R21E 1997 FSL 0638 FEL
		BHL Sec 22 T09S R21E 1796 FSL 1580 FEL
43-047-52566	NBU 921-22J1BS	Sec 22 T09S R21E 2005 FSL 0644 FEL
		BHL Sec 22 T09S R21E 2405 FSL 1817 FEL
WELL PAD - NBU 921-22H		
43-047-52563	NBU 921-22H4CS	Sec 22 T09S R21E 2196 FNL 0627 FEL
		BHL Sec 22 T09S R21E 2403 FNL 0494 FEL
43-047-52650	NBU 921-22H1CS	Sec 22 T09S R21E 2179 FNL 0637 FEL
		BHL Sec 22 T09S R21E 1740 FNL 0494 FEL
43-047-52651	NBU 921-22A4CS	Sec 22 T09S R21E 2170 FNL 0642 FEL
		BHL Sec 22 T09S R21E 1288 FNL 0504 FEL
43-047-52652	NBU 921-22A4BS	Sec 22 T09S R21E 2162 FNL 0647 FEL
		BHL Sec 22 T09S R21E 0670 FNL 0494 FEL
43-047-52653	NBU 921-22H4BS	Sec 22 T09S R21E 2188 FNL 0632 FEL
		BHL Sec 22 T09S R21E 2071 FNL 0494 FEL

RECEIVED: May 15, 2012

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
WELL PAD - NBU 921-22E		
43-047-52568	NBU 921-22E4BS	Sec 22 T09S R21E 2179 FNL 0750 FWL
		BHL Sec 22 T09S R21E 2239 FNL 0824 FWL
43-047-52572	NBU 921-22E1BS	Sec 22 T09S R21E 2179 FNL 0720 FWL
		BHL Sec 22 T09S R21E 1576 FNL 0824 FWL
43-047-52573	NBU 921-22E1CS	Sec 22 T09S R21E 2179 FNL 0730 FWL
		BHL Sec 22 T09S R21E 1908 FNL 0824 FWL
43-047-52574	NBU 921-22E4CS	Sec 22 T09S R21E 2179 FNL 0740 FWL
		BHL Sec 22 T09S R21E 2572 FNL 0824 FWL
WELL PAD - NBU 921-22L		
43-047-52577	NBU 921-22K2DS	Sec 22 T09S R21E 1668 FSL 0666 FWL
		BHL Sec 22 T09S R21E 2038 FSL 1784 FWL
43-047-52582	NBU 921-22L1BS	Sec 22 T09S R21E 1660 FSL 0648 FWL
		BHL Sec 22 T09S R21E 2408 FSL 0824 FWL
43-047-52583	NBU 921-22L4BS	Sec 22 T09S R21E 1672 FSL 0675 FWL
		BHL Sec 22 T09S R21E 1744 FSL 0824 FWL
43-047-52585	NBU 921-22L1CS	Sec 22 T09S R21E 1664 FSL 0657 FWL
		BHL Sec 22 T09S R21E 2076 FSL 0824 FWL
WELL PAD - NBU 921-22O		
43-047-52578	NBU 921-22O4CS	Sec 22 T09S R21E 0269 FSL 1655 FEL
		BHL Sec 22 T09S R21E 0086 FSL 1816 FEL
43-047-52579	NBU 921-22P4BS	Sec 22 T09S R21E 0280 FSL 1606 FEL
		BHL Sec 22 T09S R21E 0581 FSL 0494 FEL
43-047-52581	NBU 921-22P4CS	Sec 22 T09S R21E 0278 FSL 1616 FEL
		BHL Sec 22 T09S R21E 0251 FSL 0494 FEL
43-047-52590	NBU 921-22O4BS	Sec 22 T09S R21E 0271 FSL 1645 FEL
		BHL Sec 22 T09S R21E 0416 FSL 1816 FEL
43-047-52612	NBU 921-22O1BS	Sec 22 T09S R21E 0276 FSL 1625 FEL
		BHL Sec 22 T09S R21E 1079 FSL 1817 FEL
43-047-52613	NBU 921-22O1CS	Sec 22 T09S R21E 0274 FSL 1635 FEL
		BHL Sec 22 T09S R21E 0747 FSL 1816 FEL
WELL PAD - NBU 921-22M		
43-047-52586	NBU 921-22M1BS	Sec 22 T09S R21E 0695 FSL 0660 FWL
		BHL Sec 22 T09S R21E 1080 FSL 0823 FWL
43-047-52587	NBU 921-22M1CS	Sec 22 T09S R21E 0686 FSL 0654 FWL
		BHL Sec 22 T09S R21E 0748 FSL 0823 FWL
43-047-52588	NBU 921-22M4BS	Sec 22 T09S R21E 0678 FSL 0649 FWL
		BHL Sec 22 T09S R21E 0416 FSL 0823 FWL
43-047-52589	NBU 921-22M4CS	Sec 22 T09S R21E 0670 FSL 6043 FWL
		BHL Sec 22 T09S R21E 0086 FSL 0823 FWL

RECEIVED: May 15, 2012

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management, ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2012.05.15 07:17:01 -06'00'

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:5-14-12

RECEIVED: May 15, 2012

API Well Number: 43047526500000

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 4/27/2012 **API NO. ASSIGNED:** 43047526500000

WELL NAME: NBU 921-22H1CS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6356

CONTACT: Laura Abrams

PROPOSED LOCATION: SENE 22 090S 210E **Permit Tech Review:** ☑

SURFACE: 2179 FNL 0637 FEL **Engineering Review:** ☑

BOTTOM: 1740 FNL 0494 FEL **Geology Review:** ☑

COUNTY: UINTAH

LATITUDE: 40.02285 **LONGITUDE:** -109.53065

UTM SURF EASTINGS: 625384.00 **NORTHINGS:** 4431327.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 010950-A **PROPOSED PRODUCING FORMATION(S):** BLACKHAWK

SURFACE OWNER: 2 - Indian **COALBED METHANE:** NO

RECEIVED AND/OR REVIEWED:

- ☑ **PLAT**
- ☑ **Bond:** FEDERAL - WYB000291
- ☐ **Potash**
- ☑ **Oil Shale 190-5**
- ☐ **Oil Shale 190-3**
- ☐ **Oil Shale 190-13**
- ☑ **Water Permit:** 43-8496
- ☐ **RDCC Review:**
- ☐ **Fee Surface Agreement**
- ☑ **Intent to Commingle**

Commingling Approved

LOCATION AND SITING:

- ☐ **R649-2-3.**

Unit: NATURAL BUTTES

- ☐ **R649-3-2. General**
- ☐ **R649-3-3. Exception**
- ☑ **Drilling Unit**

Board Cause No: Cause 173-14

Effective Date: 12/2/1999

Siting: Suspends General Siting

- ☑ **R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations:
3 - Commingling - ddoucet
4 - Federal Approval - dmason
15 - Directional - dmason
17 - Oil Shale 190-5(b) - dmason

RECEIVED: May 30, 2012

GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

****

Well Name: NBU 921-22H1CS
API Well Number: 43047526500000
Lease Number: UTU 010950-A
Surface Owner: INDIAN
Approval Date: 5/30/2012

Issued to:
KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:
Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the BLACKHAWK Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:
This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:
In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:
Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:
State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:
The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284
  (please leave a voicemail message if not available)
  OR
  submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
  at http://oilgas.ogm.utah.gov

Reporting Requirements:
All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

For John Rogers
Associate Director, Oil & Gas

Form 3160-3
(August 2007)

RECEIVED

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

JAN 10 2012

BLM, Vernal Utah

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: ☒ DRILL ☐ REENTER	5. Lease Serial No. UTU010950A
	6. If Indian, Allottee or Tribe Name
	7. If Unit or CA Agreement, Name and No. UTU63047A
1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone	8. Lease Name and Well No. NBU 921-22H1CS
2. Name of Operator KERR MCGEE OIL&GAS ONSHORE LP Contact: LAURA ABRAMS E-Mail: Laura.Abrams@anadarko.com	9. API Well No. 43-047-52650
3a. Address PO BOX 173779 DENVER, CO 80202-3779 / 3b. Phone No. (include area code) Ph: 720-929-6356 Fx: 720-929-7356	10. Field and Pool, or Exploratory NATURAL BUTTES
4. Location of Well *(Report location clearly and in accordance with any State requirements.*)* At surface SENE 2179FNL 637FEL 40.022848 N Lat, 109.530693 W Lon At proposed prod. zone SENE 1740FNL 494FEL 40.024054 N Lat, 109.530187 W Lon	11. Sec., T., R., M., or Blk. and Survey or Area Sec 22 T9S R21E Mer SLB
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 45.0 MILES SOUTH OF VERNAL, UT	12. County or Parish UINTAH / 13. State UT
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 494' / 16. No. of Acres in Lease 800.00	17. Spacing Unit dedicated to this well
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 319' / 19. Proposed Depth 11080 MD 11043 TVD	20. BLM/BIA Bond No. on file WYB000291
21. Elevations (Show whether DF, KB, RT, GL, etc. 4827 GL / 22. Approximate date work will start 06/30/2012	23. Estimated duration 60-90 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) LAURA ABRAMS Ph: 720-929-6356	Date 12/21/2011
Title REGULATORY ANALYST II		
Approved by (Signature)	Name (Printed/Typed) Jerry Kenczka	Date OCT 16 201
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached. CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #126496 verified by the BLM Well Information System
For KERR MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal

NOTICE OF APPROVAL

RECEIVED
OCT 19 2012
DIV. OF OIL, GAS & MINING

UDOGM

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

171KBR0190AS

NO NOS

UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE
170 South 500 East VERNAL, UT 84078 (435) 781-4400

CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	**Kerr McGee Oil & Gas Onshore, LP**	**Location:**	**SENE, Sec. 22, T9S, R21E**
Well No:	**NBU 921-22H1CS**	**Lease No:**	**UTU-010950A**
API No:	**43-047-52650**	**Agreement:**	**Natural Butte**

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	-	The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	-	Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to:blm_ut_vn_opreport@blm.gov.
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)

- Paint facilities "Shadow Gray"
- Conduct a raptor survey prior to construction operation if such activates would take place during raptor nesting season (January 1- September 30). If active raptor nests are identified during the survey, operations should be conducted according to the seasonal restrictions detailed in the Uinta Basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah
- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor construction operation with a permitted archaeologist.
- Construct temper fence around archaeological site boundary during construction
- Double line reserve pit.
- Divert existing drainage, constructing a meandering route, around the well pad. Obtain Section 404 permit prior to construction and comply with is specified mitigation measures.
- Use closed loop drilling system if possible.
- Armor corners #2 and #4 in front of diversion ditch.

DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)

SITE SPECIFIC DOWNHOLE COAs:

- A copy of Kerr McGee's Standard Operating Practices (SOP version: dated 7/17/08 and approved 7/28/08) shall be on location.
- Surface casing cement shall be brought to surface.
- Production casing cement shall be brought 200' up and into the surface casing.
- Electronic/mechanical mud monitoring equipment shall be required, from surface casing shoe to TD, which shall include as a minimum: pit volume totalizer (PVT); stroke counter; and flow sensor.
- Require usage of a modified 5m stack. The 5M BOPE (minimum) shall be a modified 5m BOPE stack to include a third (3) pipe ram and one (1) remote kill line.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. *The following items are emphasized:*

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.

- No aggressive/fresh hard-banded drill pipe shall be used within casing.

- **Cement baskets shall not be run on surface casing.**

- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.

- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.

- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**

- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.

- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:

    - Operator name, address, and telephone number.

    - Well name and number.

    - Well location (¼¼, Sec., Twn, Rng, and P.M.).

    - Date well was placed in a producing status (date of first production for which royalty will be paid).

    - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).

    - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.

    - Unit agreement and/or participating area name and number, if applicable.

    - Communitization agreement number, if applicable.

- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.

- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.

- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.

- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.

- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.

- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.

- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.

- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
✓ SPUD REPORT Date of Spud: 3/13/2013	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
☐ DRILLING REPORT Report Date:	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE WELL SPUD ON MARCH 13, 2013 AT 11:30. MIRU TRIPLE A BUCKET RIG. DRILLED 20in CONDUCTOR HOLE TO 40ft. RAN 14in 36.7lb SCHEDULE 10 CONDUCTOR PIPE. CEMENT WITH 28 SACKS READY MIX. ANTICIPATED SURFACE RIG SPUD DATE ON MARCH 31, 2013 AND CASING CEMENT MARCH 31, 2013 AT 08:00 HRS.

Accepted by the Utah Division of Oil, Gas and Mining
FOR RECORD ONLY
March 19, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Luke Urban	720 929-6501	Regulatory Specialist
SIGNATURE		**DATE**
N/A		3/18/2013

RECEIVED: Mar. 18, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP
Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217
Phone Number: (720) 929-6501

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304752563	NBU 921-22H4CS	SENE	22	9S	21E	UINTAH

Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date
B	99999	2900	3/13/2013	3/28/13

Comments: MIRU TRIPLE A BUCKET RIG.
SPUD WELL LOCATION ON March 13, 2013 AT 08:30 HRS.

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304752650	NBU 921-22H1CS	SENE	22	9S	21E	UINTAH

Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date
B	99999	2900	3/13/2013	3/28/13

Comments: MIRU TRIPLE A BUCKET RIG.
SPUD WELL LOCATION ON March 13, 2013 AT 11:30 HRS.

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304752652	NBU 921-22A4BS	SENE	22	9S	21E	UINTAH

Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date
D	99999	2900	3/13/2013	3/28/13

Comments: MIRU TRIPLE A BUCKET RIG.
SPUD WELL LOCATION ON March 13, 2013 AT 14:00 HRS.

ACTION CODES:
- **A** - Establish new entity for new well (single well only)
- **B** - Add new well to existing entity (group or unit well)
- **C** - Re-assign well from one existing entity to another existing entity
- **D** - Re-assign well from one existing entity to a new entity
- **E** - Other (Explain in 'comments' section)

Luke Urban
Name (Please Print)
Signature
Sr. Regulatory Specialist
Title
3/19/2013
Date

RECEIVED
MAR 20 2013
Div. of Oil, Gas & Mining

(5/2000)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 5/3/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No Activity for the month of April 2013. Well TD at 2,900.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
May 03, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Jaime Scharnowske	720 929-6304	Regulartory Analyst
SIGNATURE N/A		**DATE** 5/3/2013

RECEIVED: May. 03, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 6/3/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No actitivy for the month of May 2013. Well TD at Drilled to 2,900 ft.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
June 10, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Matthew P Wold	720 929-6993	Regulatory Analyst I
SIGNATURE		**DATE**
N/A		6/3/2013

RECEIVED: Jun. 03, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **PHONE NUMBER:** 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 7/5/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

No actitivy for the month of June 2013. Well TD at Drilled to 2,920 ft.

Accepted by the Utah Division of Oil, Gas and Mining
FOR RECORD ONLY
July 08, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Teena Paulo	720 929-6236	Staff Regulatory Specialist
SIGNATURE N/A		**DATE** 7/5/2013

RECEIVED: Jul. 05, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 8/5/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Drilled to 9,592 ft. in July 2013.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
August 05, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Teena Paulo	720 929-6236	Staff Regulatory Specialist
SIGNATURE		**DATE**
N/A		8/5/2013

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# HP 318 Submitted By HARMON COCKRELL Phone Number 435-828-0988/1544
Well Name/Number NBU 921-22H1CS
Qtr/Qtr SE/NE Section 22 Township 9S Range 21E
Lease Serial Number UTU 010950A
API Number 4304752650

Casing – Time casing run starts, not cementing times.

☒ Production Casing
☐ Other

Date/Time 08/02/2013 02:00 AM ☒ PM ☐

BOPE
☐ Initial BOPE test at surface casing point
☐ Other

Date/Time _____ _____ AM ☐ PM ☐

RECEIVED
JUL 3 1 2013
DIV. OF OIL, GAS & MINING

Rig Move
Location To: _____

Date/Time _____ _____ AM ☐ PM ☐

Remarks TIME IS ESTIMATED

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 9/4/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Drilled to 10,040 ft. in August 2013.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
October 02, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Teena Paulo	720 929-6236	Staff Regulatory Specialist
SIGNATURE		**DATE**
N/A		9/4/2013

RECEIVED: Sep. 04, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 10/4/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	☐ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Started completing the well. Well TD at 10,040 ft.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
October 07, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Teena Paulo	720 929-6236	Staff Regulatory Specialist
SIGNATURE		**DATE**
N/A		10/4/2013

RECEIVED: Oct. 04, 2013

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In

7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES

1. TYPE OF WELL Gas Well

8. WELL NAME and NUMBER: NBU 921-22H1CS

2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.

9. API NUMBER: 43047526500000

3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779

PHONE NUMBER: 720 929-6526

9. FIELD and POOL or WILDCAT: NATURAL BUTTES

4. LOCATION OF WELL
FOOTAGES AT SURFACE: 2179 FNL 0637 FEL
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 09.0S Range: 21.0E Meridian: S

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
☐ NOTICE OF INTENT Approximate date work will start:	☐ ACIDIZE	☐ ALTER CASING	☐ CASING REPAIR
☐ SUBSEQUENT REPORT Date of Work Completion:	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	☐ CHANGE WELL NAME
☐ SPUD REPORT Date of Spud:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE
✓ DRILLING REPORT Report Date: 10/4/2013	☐ DEEPEN	☐ FRACTURE TREAT	☐ NEW CONSTRUCTION
	☐ OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
	✓ PRODUCTION START OR RESUME	☐ RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION
	☐ REPERFORATE CURRENT FORMATION	☐ SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL
	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	☐ APD EXTENSION
	☐ WILDCAT WELL DETERMINATION	☐ OTHER	OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 10/04/2013. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.

Accepted by the Utah Division of Oil, Gas and Mining
FOR RECORD ONLY
October 11, 2013

NAME (PLEASE PRINT)	PHONE NUMBER	TITLE
Teena Paulo	720 929-6236	Staff Regulatory Specialist
SIGNATURE N/A		**DATE** 10/11/2013

API Well Number: 43047526500000

Form 3160-4
(August 2007)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.: UTU010950A

1a. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name:

7. Unit or CA Agreement Name and No.: UTU63047A

2. Name of Operator: KERR-MCGEE OIL AND GAS ONSHORE LP
Contact: TEENA PAULO
E-Mail: Teena.Paulo@anadarko.com

8. Lease Name and Well No.: NBU 921-22H1CS

3. Address: P.O. BOX 173779
DENVER, CO 82017

3a. Phone No. (include area code)
Ph: 720-929-6000

9. API Well No.: 43-047-52650

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface: SENE 2179FNL 637FEL 40.022848 N Lat, 109.530693 W Lon

At top prod interval reported below: SENE 1726FNL 504FEL

At total depth: SENE 1742FNL 495FEL

10. Field and Pool, or Exploratory: NATURAL BUTTES

11. Sec., T., R., M., or Block and Survey or Area: Sec 22 T9S R21E Mer SLB

12. County or Parish: UINTAH

13. State: UT

14. Date Spudded: 03/13/2013

15. Date T.D. Reached: 08/02/2013

16. Date Completed: ☐ D & A ☒ Ready to Prod. 10/04/2013

17. Elevations (DF, KB, RT, GL)*: 4850 KB

18. Total Depth: MD 10040 TVD 10003

19. Plug Back T.D.: MD 9957 TVD 9920

20. Depth Bridge Plug Set: MD TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
CBL/GR/CCL/TEMP

22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit analysis)
Directional Survey? ☐ No ☒ Yes (Submit analysis)

23. Casing and Liner Record *(Report all strings set in well)*

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20.000	14.000 STL	36.7	0	40		28			
11.000	8.625 J-55	28.0	24	2893		650		0	
7.875	4.500 I-80	11.6	24	4875		2005		0	
7.875	4.500 P-110	11.6	4875	10005					

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	9415							

25. Producing Intervals / 26. Perforation Record

	Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A)	MESAVERDE	7876	9834	7876 TO 9834	0.360	186	OPEN
B)							
C)							
D)							

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
7876 TO 9834	PUMP 12,072 BBL SLICKWATER AND 248,965 LBS 30/50 MESH SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
10/04/2013	10/08/2013	24	→	41.0	1611.0	0.0			FLOWS FROM WELL

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status
20/64	1257	2046.0	→	41	1611	0		PGW

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status
			→					

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #225062 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED: Oct. 31, 2013

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status
			→					

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status
			→					

29. Disposition of Gas *(Sold, used for fuel, vented, etc.)*
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
				GREEN RIVER	1590
				BIRD'S NEST	1886
				MAHOGANY	2401
				WASATCH	4948
				MESAVERDE	7841

32. Additional remarks (include plugging procedure):
The first 210 ft. of the surface hole was drilled with a 12 ? in. bit. The remainder of surface hole was drilled with an 11 in. bit. A DV tool was placed in the well from 5073 feet ? 5076 feet. DQX csg was run from surface to 4896 ft.; LTC csg was run from 4896 ft. to 10,005 ft. Attached is the chronological well history, perforation report & final survey.

33. Circle enclosed attachments:

1. Electrical/Mechanical Logs (1 full set req'd.)
2. Geologic Report
3. DST Report
4. Directional Survey
5. Sundry Notice for plugging and cement verification
6. Core Analysis
7 Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #225062 Verified by the BLM Well Information System.
For KERR-MCGEE OIL AND GAS ONSHORE, sent to the Vernal

Name *(please print)* TEENA PAULO Title STAFF REGULATORY SPECIALIST

Signature (Electronic Submission) Date 10/31/2013

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fradulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

RECEIVED: Oct. 31, 2013

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
3/19/2013	12:00 - 14:00	2.00	MIRU	01	B	P		SKID RIG 20' TO NBU 921-22H1CS, RIG UP SET MATTING BOARD, SET RIG IN PLACE, CATWALK, PIPE RACKS, PLACE BOTTOME HOLE ASSEMBLY
	14:00 - 14:30	0.50	MIRU	01	C	P		PRE SPUD JOB SAFETY MEETING REVEW DIRECTIONAL PLANS AND PLATS AND VERIFY LAT/LONGS AND WELL ORDER VERIFY DIRECTIONAL DRILLERS PLAN IS THE MOST RECENT AND APPROVED VERSION REFERENCE WELLBORE DIAGRAMS FOR EXACT CASING DESIGN AND GENERAL OVERVEW OF WELLBORE, PRIOR TO SPUD. FINISH PICKING UP BHA. PICK UP NOV 1.83 DEGREE BENT MOTOR (RUN #2) - .17 REV/GAL SN (775-77294). PICK UP 12.25 REED DRILL BIT RUN 8 SN (A147929)
	14:30 - 16:00	1.50	DRLSUR	02	B	P		SPUD @ 03/19/2013 14:30. DRILL 12.25" HOLE 44'-210' (166', 110'/PER HOUR). 12.25" BIT ON 8th RUN. WEIGHT ON BIT 5-15 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF (BOTTOM) 800/600. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROTATE 20/20/20 K. DRAG 0 K. CIRCULATE CLOSED LOOP SYSTEM WITH 8.3# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. DRILL DOWN TO 210' WITH 6" DRILL COLLARS.
	16:00 - 17:30	1.50	DRLSUR	06	A	P		PRE JOB SAFETY MEETING, CIRC 15 MINUTES AND, TRIP OUT TO CHANGE ASSEMBLY. LAY DOWN 6" DRILL COLLARS, BREAK 12 1/4" BIT. MAKE UP READ 11" BIT (8TH RUN) (SN 7142125) PICK UP 8" DIRECTIONAL ASSEMBLY. INSTALL EM TOOL, TRIP IN HOLE.

RECEIVED: Oct. 31, 2013

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW			Spud Date: 3/19/2013
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:30 - 0:00	6.50	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 210'-1140', (930', 143'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1000/830. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 60/45/50 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 8' NORTH 3' RIGHT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
3/20/2013	0:00 - 6:00	6.00	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 1140'-1680', (540', 90'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1200/1000. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 70/50/60 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 5.21' NORTH 3.37' RIGHT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
	6:00 - 7:00	1.00	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 1680'-1770', (90', 90'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1300/1100. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 75/55/65 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 5.21' NORTH 3.37' RIGHT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
	7:00 - 8:00	1.00	DRLSUR	22	L	Z		***FAILURE: MWD DEPTH 1770' LOST COMMUNICATION WITH MWD TOOL.

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW			Spud Date: 3/19/2013
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	8:00 - 12:00	4.00	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 1770'-2100', (330', 82'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1350/1150. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 80/60/70 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 4.76' NORTH .63' LEFT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
	12:00 - 18:00	6.00	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 2100'-2580', (480', 80'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1450/1200. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 85/65/75 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 3.03' NORTH 1.09' LEFT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
	18:00 - 23:30	5.50	DRLSUR	02	B	P		DRILL 11". SURFACE HOLE 2580'-2900', (320', 58'/PER HOUR). WEIGHT ON BIT 18-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1450/1200. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 85/65/75 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 7' SOUTH 3' RIGHT OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.
	23:30 - 0:00	0.50	DRLSUR	05	C	P		CIRCULATE AND CONDITION HOLE FOR CASING RUN.

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
3/21/2013	0:00 - 1:30	1.50	DRLSUR	05	A	P		CIRCULATE AND CONDITION HOLE, VOLUME IS CLEAN COMING OVER SHAKERS, 4-400 BBL UPRIGHT'S FULL AND 2-400 BBL UPRIGHTS EMPTY, MUD TANKS FULL.
	1:30 - 6:00	4.50	CSGSUR	06	D	P		TRIP OUT OF HOLE, LAY DOWN DRILL STRING, BOTTOM HOLE ASSEMBLY, DIRECTIONAL TOOLS, MOTOR AND, BIT. CLEAR TOOL AREA.
	6:00 - 7:00	1.00	CSGSUR	06	D	P		PRE JOB SAFETY MEETING, MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN SURFACE CASING. CLEAR UNRELATED TOOLS.
	7:00 - 8:30	1.50	CSGSUR	12	C	P		RUN 65 JOINTS OF 8-5/8". 28# J-55 LTC CASING. RAN 1 CENTRALIZER ON FIRST THREE JOINTS, AND EVERY OTHER JOINT FOR 2 JOINTS FOR A TOTAL OF 5 CENTRALIZERS. RUN A TOTAL OF 65 JOINTS. RUN CASING TO BOTTOM WITH NO PROBLEMS. SET FLOAT SHOE @ 2873.44' KB. SET TOP OF BAFFLE PLATE @ 2827.29' KB.
	8:30 - 11:00	2.50	CSGSUR	12	E	P		PRE JOB SAFETY MEETING, RELEASE RIG @ 03/21/2013 11:00 RAN 200 ft OF 1 lin. PIPE DOWN BACK-SIDE OF CASING. PRESSURE TEST LINES TO 2000 PSI. PUMP 170 BBLS OF WATER AHEAD CLEARING THE SHOE. MIX AND PUMP 20 BBLS OF 8.5# GEL WATER AHEAD. MIX AND PUMP (300 sx) 152.8 BBLS OF 12.0# 2.86 YIELD LEAD CEMENT. MIX AND PUMP (200 sx) 40.9 BBLS OF 15.8# 1.15 YIELD TAIL CEMENT. DROP PLUG ON FLY, DISPLACE WITH 176 BBLS OF H2O, FULL RETURNS THROUGH OUT JOB, FINAL LIFT OF 350 PSI AT 3 BBL/MINUTE. BUMP THE PLUG WITH 630 PSI, HELD 630 PSI FOR 5 MINUTES, TESTED FLOAT AND FLOAT HELD. SHUT DOWN AND WASH UP. PUMP CEMENT DOWN ONE INCH PIPE WITH 150 sx (32.7 bbls.)SAME TAIL CEMENT, 1 BBL RETURNS TO SURFACE, CEMENT HELD AT SURFACE. SHUT DOWN AND WASH UP. RIG DOWN CEMENTERS. (CEMENT JOB FINISHED @ 03/21/2013 12:00)
7/27/2013	18:00 - 19:00	1.00	RDMO	01	E	P		RIG DOWN PREP TO SKID RIG
	19:00 - 19:30	0.50	RDMO	01	C	P		SKID RIG TO NBU 921-22H1CS
	19:30 - 20:00	0.50	RDMO	01	B	P		RIG UP ROTARY TOOLS
	20:00 - 21:00	1.00	DRLPRC	14	A	P		NIPPLE UP BOPS
	21:00 - 21:30	0.50	DRLPRC	15	A	P		TEST 8 5/8 CASING 1500 PSI FOR 30 MINS

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013
Project: UTAH-UINTAH	Site: NBU 921-22H PAD	Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013	End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	21:30 - 0:00	2.50	DRLPRC	15	A	P		TESTING BOPS LOW 250 PSI FOR 5 MINS HIGH FOR 10 MINS BLINDS, PIPE RAMS, HCR, IBOP, FLOOR VAVLES, WING VAVLES, CHOKE MANIFOLD
7/28/2013	0:00 - 0:30	0.50	RDMO	15	A	P		FINSH TESTING HY-DRILL LOW 250 HIGH 2500 PSI
	0:30 - 1:00	0.50	RDMO	15	A	P		TEST SWACO LINES TO 1,000 PSI
	1:00 - 1:30	0.50	RDMO	15	A	P		INSTALL WEAR BUSHING
	1:30 - 3:00	1.50	RDMO	09	A	P		SLIP & CUT DRILLING LINE 88' FUNCTION TEST CROWN SAVER
	3:00 - 4:30	1.50	RDMO	06	A	P		P/U BHA ,MWD TOOLS SCRIBE INHOLE
	4:30 - 6:00	1.50	RDMO	06	A	P		TIH TAGED TOP CMT @ 2814
	6:00 - 7:30	1.50	DRLPRC	02	F	P		DRILL CMT & SHOE TRACK
	7:30 - 12:00	4.50	DRLPRC	02	D	P	2920	DRILL (ROTATE/SLIDE) F/2920 '-T 3570 RATE OF PENATRATION= 650' @ 144.44 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 69 ~ TOTAL= 166 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1900 / 1450 TORQUE~ ON/OFF = 8,000 / 3,000 PICKUP/SLACK OFF/ROTATE= 115K / 88K / 98K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE SLIDE 38 ' 0 HRS. 40 MINS BIT POSITION= 21.7' WEST & 13.03 NORTH OF TARGET LINE LAST SURVEY @ 3517 '= 3.5 DEG.,9.07 AZ., 3480.83 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
	12:00 - 16:30	4.50	DRLPRC	02	D	P	3570	DRILL (ROTATE/SLIDE) F/ 3570 '-T 4238 RATE OF PENATRATION= 668' @ 148.44 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 69 ~ TOTAL= 166 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1950 / 1350 TORQUE~ ON/OFF = 8,000 / 3,000 PICKUP/SLACK OFF/ROTATE= 115K / 88K / 98K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 200 PSI CON. 175 PSI DRILLING SLIDE 30 ' 0 HRS. 35 MINS BIT POSITION= 18.15' WEST & 15.31 NORTH OF TARGET LINE LAST SURVEY @ 4178 '= .8 DEG., 184.14 AZ., 4141.68 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE BOP DRILL 3 MINS 25 SEC.
	16:30 - 17:00	0.50	DRLPRC	07	A	P		RIG SER.

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:00 - 0:00	7.00	DRLPRV	02	D	P	4238	DRILL (ROTATE/SLIDE) F/ 4238 '-T 5083 RATE OF PENATRATION= 845' @ 120.71 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 69 ~ TOTAL= 166 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1725 / 1375 TORQUE~ ON/OFF = 9,000 / 6,000 PICKUP/SLACK OFF/ROTATE= 144K / 104K / 127K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 200 PSI CON. 175 PSI DRILLING SLIDE 51 ' 1.5 HRS. 0 MINS BIT POSITION= 18.4' WEST & 11.51 NORTH OF TARGET LINE LAST SURVEY @ 5121 '= 0.88 DEG.,36.93 AZ., 5084.63 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
7/29/2013	0:00 - 6:00	6.00	DRLPRV	02	B	P	5083	DRILL (ROTATE/SLIDE) F/ 5083 '-T 5841 RATE OF PENATRATION= 758' @ 126.33 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1725 / 1375 TORQUE~ ON/OFF = 9,000 / 6,000 PICKUP/SLACK OFF/ROTATE= 144K / 104K / 127K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 270 PSI CON. 250 PSI DRILLING SLIDE 0 ' 0 HRS. 0 MINS BIT POSITION= 12.73' WEST & 14.02 NORTH OF TARGET LINE LAST SURVEY @ 5594 '= 0.64 DEG., 98.45AZ., 557.61 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	6:00 - 12:00	6.00	DRLPRV	02	B	P	5841	DRILL (ROTATE/SLIDE) F/ 5841 '-T 6417 RATE OF PENATRATION= 576' @ 96.00 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1870 / 1600 TORQUE~ ON/OFF = 10,000 / 7,000 PICKUP/SLACK OFF/ROTATE= 178K / 121K / 148K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 250 PSI CON. 250 PSI DRILLING SLIDE 11 ' 0 HRS. 25 MINS BIT POSITION= 10.58' WEST & 16.02 NORTH OF TARGET LIINE LAST SURVEY @ 6350 '= .80 DEG., 149.77 AZ., 6313.54 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
	12:00 - 16:30	4.50	DRLPRV	02	B	P	6417	DRILL (ROTATE/SLIDE) F/ 6417 '-T 6785 RATE OF PENATRATION= 368' @ 81.77 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1870 / 1600 TORQUE~ ON/OFF = 10,000 / 7,000 PICKUP/SLACK OFF/ROTATE= 178K / 121K / 148K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 250 PSI CON. 250 PSI DRILLING SLIDE 22 ' 1 HRS. 5 MINS BIT POSITION= 11.07' WEST & 13.07 NORTH OF TARGET LIINE LAST SURVEY @ 6727 '= 0.60 DEG., 279.02 AZ., 6690.52 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
	16:30 - 17:00	0.50	DRLPRV	07	A	P		RIG SER

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013
Project: UTAH-UINTAH	Site: NBU 921-22H PAD	Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013	End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:00 - 0:00	7.00	DRLPRV	02	B	P	6785	DRILL (ROTATE/SLIDE) F/ 6785 '-T 7255 RATE OF PENATRATION= 470' @ 67.14 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1870 / 1700 TORQUE~ ON/OFF = 10,000 / 9,000 PICKUP/SLACK OFF/ROTATE= 198K / 129K / 160K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 350 PSI CON. 350 PSI DRILLING SLIDE 11 ' 0 HRS. 25 MINS BIT POSITION= 12.07' WEST & 10.74NORTH OF TARGET LIINE LAST SURVEY @ 7199 '= 0.44 DEG., 49.06 AZ., 7162.5 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
7/30/2013	0:00 - 6:00	6.00	DRLPRV	02	B	P	7255	DRILL (ROTATE/SLIDE) F/ 7255 '-T 7540 RATE OF PENATRATION= 285' @ 47.5 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 1870 / 1700 TORQUE~ ON/OFF = 10,000 / 9,000 PICKUP/SLACK OFF/ROTATE= 198K / 129K / 160K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 350 PSI CON. 350 PSI DRILLING SLIDE 0 ' 0 HRS. 0 MINS BIT POSITION= 10.82' WEST & 11.85NORTH OF TARGET LIINE LAST SURVEY @ 7388 '= 0.35 DEG., 88.17 AZ., 7351.49 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	6:00 - 12:00	6.00	DRLPRV	02	B	P	7540	DRILL (ROTATE/SLIDE) F/ 7540 '-T 7880 RATE OF PENATRATION= 340' @ 56.66 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2100 / 1850 TORQUE~ ON/OFF = 11,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 208K / 134K / 160K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 350 PSI CON. 350 PSI DRILLING SLIDE 10 ' 0 HRS. 30 MINS BIT POSITION= 9.38' WEST & 13.83NORTH OF TARGET LIINE LAST SURVEY @ 7766 '= .40 DEG., 49.22 AZ., 7729.48 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
	12:00 - 17:30	5.50	DRLPRV	02	B	P	7880	DRILL (ROTATE/SLIDE) F/ 7880 '-T 8202 RATE OF PENATRATION= 322' @ 58.54 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 60 ~ TOTAL= 157 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2100 / 1850 TORQUE~ ON/OFF = 11,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 208K / 134K / 165K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 13 ' 0 HRS. 50 MINS BIT POSITION= 7.78' WEST & 13.87 NORTH OF TARGET LIINE LAST SURVEY @ 8144 '= .53 DEG., 292.60 AZ., 8107.47 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
	17:30 - 18:00	0.50	DRLPRV	07	A	P		RIG SER.

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	18:00 - 0:00	6.00	DRLPRV	02	B	P	8202	DRILL (ROTATE/SLIDE) F/ 8202 '-T 8548 RATE OF PENATRATION= 346' @ 57.66 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2100 / 1850 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 228K / 139K / 176K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 12 ' 0 HRS. 40 MINS BIT POSITION= 8.65' WEST & 13.62 NORTH OF TARGET LIINE LAST SURVEY @ 8521 '= 0.21 DEG. 36.93 AZ., 8484.47 ' TVD 0 BBLS MUD LOST TO SEEPAGE @ 0' DRILLING FLARE // ' CONNECTION FLARE
7/31/2013	0:00 - 6:00	6.00	DRLPRV	02	B	P	8548	DRILL (ROTATE/SLIDE) F/ 8548'-T 8862 RATE OF PENATRATION= 314' @ 52.33 ' /HR WEIGHT ON BIT = 25 / K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2170 / 1920 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 228K / 139K / 176K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 12 ' 0 HRS. 30 MINS BIT POSITION= 7.71' WEST & 13.68NORTH OF TARGET LIINE LAST SURVEY @ 8710 '= .35 DEG., 101.44 AZ., 8673.46 ' TVD 60 BBLS MUD LOST TO SEEPAGE @ 8202 0' DRILLING FLARE // ' CONNECTION FLARE

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	6:00 - 12:00	6.00	DRLPRV	02	B	P	8862	DRILL (ROTATE/SLIDE) F/ 8862'-T/ 9151' RATE OF PENATRATION= 289' @ 48.2' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2170 / 1920 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 244K / 140K / 183K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 11' / 50 MINS BIT POSITION= 4.59' WEST & 12.38 NORTH OF TARGET LIINE LAST SURVEY @ 9087'= .95 DEG., 128.45 AZ., 9050' TVD 20 BBLS MUD LOST TO SEEPAGE @ 8202 0' DRILLING FLARE // ' CONNECTION FLARE
	12:00 - 15:00	3.00	DRLPRV	02	B	P	9152	DRILL (ROTATE/SLIDE) F/ 9151'- T/ 9334' RATE OF PENATRATION= 183' @ 61' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2235 / 2070 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 248K / 144K / 187K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 0 0' DRILLING FLARE // ' CONNECTION FLARE
	15:00 - 15:30	0.50	DRLPRV	07	A	P		SERVICE RIG & EQUIPMENT
	15:30 - 18:00	2.50	DRLPRV	02	B	P	9334	DRILL (ROTATE/SLIDE) F/ 9334'- T/ 9491 RATE OF PENATRATION= 157' @ 62.8' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2235 / 2070 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 249K / 143K / 188K MUD WEIGHT= 8.6 / VISCOSITY= 29 NOV DEWATERING SWACO ON LINE TRAP 450 PSI CON. 475 PSI DRILLING SLIDE 0 0' DRILLING FLARE // ' CONNECTION FLARE

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	18:00 - 21:30	3.50	DRLPRV	02	B	P	9491	DRILL (ROTATE/SLIDE) F/ 9491' -T/ 9574' RATE OF PENATRATION= 83' @ 23.7' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR =97 TOP DRIVE= 62 ~ TOTAL= 159 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2235 / 2070 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 249K / 143K / 188K MUD WEIGHT= 10.5 / VISCOSITY= 37 NOV OFF LINE SWACO OFF LINE SLIDE MINS 0' DRILLING FLARE // ' CONNECTION FLARE START DISPLACING HEAVY MUD INTO HOLE IN STAGES / DISPLACE 10.5 ppg, 38 VISC IN HOLE & TAKE SWACO OFF LINE / START DISPLACEING 12.0 ppg INTO HOLE & LOST RETURNS / HOLE STICKY ON BOTTOM
	21:30 - 23:00	1.50	DRLPRV	05	A	X		*** PULL 2 STANDS // REGAIN CIRCULATION // BUILD VOLUME & CONDITION MUD TO 12.0 ppg , 38 VISC, & 8% LCM
	23:00 - 0:00	1.00	DRLPRV	02	B	P	9574	DRILL (ROTATE/SLIDE) F/ 9574'- T/ 9592' RATE OF PENATRATION= 18' @ 18' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR = 94 TOP DRIVE= 62 ~ TOTAL= 154 GALLONS PER MINUTE = 450 STROKES PER MINUTE = 100 STAND PIPE PSI~0N/OFF = 2350 / 2100 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 235K / 160K / 190K MUD WEIGHT= 12.1 / VISCOSITY= 38 NOV OFF LINE SWACO OFF LINE SLIDE 0 BIT POSITION= 2.94' WEST & 8.48 NORTH OF TARGET LIINE LAST SURVEY @ 9653'= 1.09 DEG., 183.18 AZ., 9616' TVD 350 BBL'S TOTAL LOST ON TRANSFER 0' DRILLING FLARE // ' CONNECTION FLARE WELL FLOWING ON CONNECTIONS

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013		End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
8/1/2013	0:00 - 6:00	6.00	DRLPRV	02	B	P	9592	DRILL (ROTATE/SLIDE) F/ 9592'- T/ 9774' RATE OF PENATRATION= 182' @ 30.3' /HR WEIGHT ON BIT = 25 / 26K RPM ~ MUD MOTOR = 94 TOP DRIVE= 62 ~ TOTAL= 154 GALLONS PER MINUTE = 450 STROKES PER MINUTE = 100 STAND PIPE PSI~0N/OFF = 2350 / 2100 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 235K / 160K / 190K MUD WEIGHT= 12.2 / VISCOSITY= 38 // 8% LCM NOV OFF LINE SWACO OFF LINE SLIDE 0 BIT POSITION= 2.94' WEST & 8.48 NORTH OF TARGET LIINE LAST SURVEY @ 9653'= 1.09 DEG., 183.18 AZ., 9616' TVD 0' DRILLING FLARE // ' CONNECTION FLARE WELL FLOWING ON CONNECTIONS
	6:00 - 10:00	4.00	DRLPRV	02	B	P	9774	3DRILL (ROTATE/SLIDE) F/ 9774'-T/ 9885' RATE OF PENATRATION= 111' @ 27.75' /HR WEIGHT ON BIT = 25 / 28K RPM ~ MUD MOTOR = 104 TOP DRIVE= 65 ~ TOTAL= 170 GALLONS PER MINUTE = 495 STROKES PER MINUTE = 110 STAND PIPE PSI~0N/OFF = 2350 / 2100 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 235K / 160K / 190K MUD WEIGHT= 12.3 / VISCOSITY= 38 // 8% LCM NOV OFF LINE SWACO OFF LINE BIT POSITION = 2.72' WEST & 3.87' NORTH OF TARGET LINE LAST SURVEY @ 9748' = .98 DEG., 1.63.63 AZ., 9711' TVD NO FLARE ROP DROPPED OFF TO 12' PER HOUR
	10:00 - 10:30	0.50	DRLPRV	05	A	P		CIRCULATE & PREPARE FLOOR TO TRIP
	10:30 - 11:00	0.50	DRLPRV	07	A	P		SERVICE RIG & EQUIPMENT
	11:00 - 15:00	4.00	DRLPRV	06	A	P		TRIP FOR BIT #1
	15:00 - 17:00	2.00	DRLPRV	22	M	X		*** WORK TIGHT HOLE F/ 4830'-T/ 4880'
	17:00 - 20:00	3.00	DRLPRV	06	A	P		TRIP FOR BIT #1
	20:00 - 21:30	1.50	DRLPRV	06	A	P		INSPECT BIT #1 & MUD MOTOR // LAY DOWN SAME & PICK UP BIT # 2 & NEW MUD MOTOR
	21:30 - 0:00	2.50	DRLPRV	06	A	P		TRIP IN HOLE WITH BIT #2
8/2/2013	0:00 - 3:30	3.50	DRLPRV	06	A	P		TRIP IN HOLE WITH BIT #2 // BRIDGES @ 3586', 4445', 4920', 5590' // TIGHT FROM 4920' T/ 6200'
	3:30 - 5:00	1.50	DRLPRV	03	D	P		WASH & REAM F/ 9230'-T/ 9885' (PRECAUTIONARY)

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013
Project: UTAH-UINTAH	Site: NBU 921-22H PAD	Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013	End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	5:00 - 7:00	2.00	DRLPRV	02	B	P	9885	DRILL (ROTATE/SLIDE) F/ 9885' -T/ 10040' RATE OF PENATRATION= 155' @ 77.5' /HR WEIGHT ON BIT = 24K RPM ~ MUD MOTOR = 95 TOP DRIVE= 65 ~ TOTAL= 160 GALLONS PER MINUTE = 450 STROKES PER MINUTE = 100 STAND PIPE PSI~0N/OFF = 2350 / 2100 TORQUE~ ON/OFF = 12,000 / 10,000 PICKUP/SLACK OFF/ROTATE= 235K / 160K / 190K MUD WEIGHT= 12.3 / VISCOSITY= 38 // 8% LCM NOV OFF LINE SWACO OFF LINE BIT POSITION = .39' EAST & 2.28' SOUTH OF TARGET LINE LAST SURVEY @ 9982' = 1.88 DEG., 149.47 AZ., 9945' TVD NO FLARE LOST 80 BBL,S TO SEEPAGE
	7:00 - 8:30	1.50	DRLPRV	05	A	P		CIRCULATE & CONDITION HOLE FOR CASING
	8:30 - 16:00	7.50	DRLPRV	06	A	P		TRIP OUT OF HOLE TO RUN 4.5" CASING /// LAY DOWN DIRECTIONAL TOOLS
	16:00 - 16:30	0.50	CSGPRO	14	B	P		PULL WEAR BUSHING
	16:30 - 17:30	1.00	CSGPRO	12	A	P		SAFETY MEETING WITH KIMZEY CASING CREW & RIG UP CASING TOOLS
	17:30 - 0:00	6.50	CSGPRO	12	C	P		RUN 115 JT'S, 4.5", 11.6#, P110, LT&C CSG & 110 JT'S, 4.5", 11.6#, I-80, DQX CSG /// SHOE SET @ 10,005' /// TOP OF FLOAT COLLAR @ 9957' /// TOP OFF MARKER JT @ 7740' /// TOP OF DV TOOL @ 5073' /// TOP LTC x DQX CROSSOVER @ 4874'
8/3/2013	0:00 - 1:00	1.00	CSGPRO	12	C	P		RUN 115 JT'S, 4.5", 11.6#, P110, LT&C CSG & 110 JT'S, 4.5", 11.6#, I-80, DQX CSG /// SHOE SET @ 10,005' /// TOP OF FLOAT COLLAR @ 9957' /// TOP OFF MARKER JT @ 7740' /// TOP OF DV TOOL @ 5073' /// TOP LTC x DQX CROSSOVER @ 4874' (WASH THROUGH BRIDGE @ 9740'
	1:00 - 2:30	1.50	CSGPRO	05	A	P		CIRCULATE CASING @ 10005' WITH 80 spm, 360 gpm & 800 PSI // 10' FLARE FOR 5 MINUTES
	2:30 - 4:30	2.00	CSGPRO	12	E	P		TEST LINES TO 4500 PSI /// PUMP FIRST STAGE - PUMPED 25 BBL FRESH WATER AHEAD // 1st TAIL CMT WITH 1160 sx (279 bbls) 50:50 POZ CEMENT @ 14.3 # WT. & 1.35 cf/sk YIELD +.05%BWOC OF STATIC FREE + 10% BWOWSODIUM CHLORIDE +.55% BWOC R-3 +.5% BWOC EC -1 +.25% LBS/SX CELLO FLAKE +.002GPS FP-6L + .7% BWOC SODIUM METASILICATE +2% BWOC BENTONITE II + 5LBS/SX KOL-SEAL, 50 LB BAG + 55.9% FRESH WATER // DISPLACE WITH 90 BBLS WATER FOLLOWED BY 64 BBLS BBL'S OF 12.3 #, 40 VISC. MUD /// BUMPED PLUG @ 04:24 08/03/2013 WITH 2775PSI /// FINAL LIFT= 2200 PSI /// CHECK FLOATS- HELD WITH 2.5 bbls BACK /// FULL RETURNS THRU OUT JOB /// PUMPED 40% EXCESS ON CEMENT /// JOB COMPLETED WITH NO ISSUES

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW	Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD	Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	Start Date: 3/7/2013	End Date: 8/3/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	4:30 - 8:30	4.00	CSGPRO	05	A	P		DROP BOMB & OPEN DV TOOL WITH 500 PSI /// CIRCULATE BETWEEN CEMENT STAGES WITH 50spm, 225 GPM, 230 psi /// 35 BBL'S CEMENT TO SURFACE
	8:30 - 10:30	2.00	CSGPRO	12	E	P		PUMP SECOND STAGE CMT. /// SPACER 25 BBLS H20 /// 2nd LEAD CMT = 795sx(252 bbls) PREMIUM LITE II CMT @ 13.00# & 1.78 cf/sx YIELD +.05% BWOC STATIC FREE + 2% BWOC CALCIUM CHLORIDE + .25 lbs/sx CELLO FLAKE + 5 lbs/sx KOL-SEAL, 50LB BAG + .4% BWOCFL-52 + .4% BWOC SODIUM METASSILICATE + 6% BWOC BENTONITE II + 101.2% FRESH WATER /// TAIL CMT = 50sx (10.3 bbls) CLASS G CMT @15.8# WT & 1.16 cf/sx YIELD + 1%BWOC CALCIUM CHLORIDE + .4% BWOC SODIUM METASILICATE + 44.4% FRESH WATER /// DROP PLUG & DISPLACE W/ 79 BBLS WATER /// BUMP PLUG @ 10:19 08/03/2013 WITH 2950 PSI /// FINAL LIFT = 1450 PSI /// CHECK FLOATS- HELD WITH 1.5 BBLS BACK TO TRUCK /// 20 BBL'S CEMENT TO SURFACE // ESTIMATED TOP OF TAIL= 4826'
	10:30 - 12:00	1.50	CSGPRO	12	B	P		FLUSH BOPE & RIG DOWN CEMENT EQUIPMENT
	12:00 - 12:30	0.50	CSGPRO	14	B	P		SET PACK OFF & LAY DOWN LANDING JOINT
	12:30 - 13:00	0.50	CSGPRO	14	A	P		NIPPLE DOWN BOPE /// RELEASE RIG @ 13:00 08/03/2013 TO THE NBU 921-22A4CS

1 General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	NBU 921-22H1CS YELLOW	**Wellbore No.**	OH
Well Name	NBU 921-22H1CS	**Wellbore Name**	NBU 921-22H1CS
Report No.	1	**Report Date**	9/23/2013
Project	UTAH-UINTAH	**Site**	NBU 921-22H PAD
Rig Name/No.		**Event**	COMPLETION
Start Date	9/4/2013	**End Date**	10/4/2013
Spud Date	3/19/2013	**Active Datum**	RKB @4,850.00usft (above Mean Sea Level)
UWI	SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

1.3 General

Contractor		**Job Method**		**Supervisor**	
Perforated Assembly		**Conveyed Method**			

1.4 Initial Conditions

Fluid Type		**Fluid Density**	
Surface Press		**Estimate Res Press**	
TVD Fluid Top		**Fluid Head**	
Hydrostatic Press		**Press Difference**	
Balance Cond	NEUTRAL		

1.5 Summary

Gross Interval	7,876.0 (usft)-9,834.0 (usft	**Start Date/Time**	9/23/2013 12:00AM
No. of Intervals	51	**End Date/Time**	9/23/2013 12:00AM
Total Shots	186	**Net Perforation Interval**	54.00 (usft)
Avg Shot Density	3.44 (shot/ft)	**Final Surface Pressure**	
		Final Press Date	

2 Intervals

2.1 Perforated Interval

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
9/23/2013 12:00AM	MESAVERDE/			7,876.0	7,878.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
9/23/2013 12:00AM	MESAVERDE/			7,908.0	7,910.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			7,934.0	7,935.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,002.0	8,003.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,050.0	8,052.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,109.0	8,110.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,130.0	8,131.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,158.0	8,159.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,183.0	8,184.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,206.0	8,207.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,258.0	8,259.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,296.0	8,297.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,320.0	8,321.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,396.0	8,397.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,499.0	8,500.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,552.0	8,553.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,574.0	8,575.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,643.0	8,644.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,680.0	8,681.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,808.0	8,809.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,829.0	8,830.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,850.0	8,851.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
9/23/2013 12:00AM	MESAVERDE/			8,867.0	8,868.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,930.0	8,931.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,946.0	8,947.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			8,993.0	8,994.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,085.0	9,086.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,102.0	9,103.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,116.0	9,117.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,140.0	9,141.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,194.0	9,195.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,228.0	9,229.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,280.0	9,281.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,290.0	9,291.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,309.0	9,310.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,374.0	9,375.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,403.0	9,404.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,447.0	9,448.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,478.0	9,479.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,504.0	9,505.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,554.0	9,555.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,604.0	9,605.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,614.0	9,615.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-TS (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
9/23/2013 12:00AM	MESAVERDE/			9,626.0	9,627.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,640.0	9,641.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,700.0	9,701.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,712.0	9,713.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,734.0	9,735.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,762.0	9,763.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,780.0	9,781.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	
9/23/2013 12:00AM	MESAVERDE/			9,833.0	9,834.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTION	

3 Plots

3.1 Wellbore Schematic



US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: SWABBCO 6/6
Event: COMPLETION	Start Date: 9/4/2013		End Date: 10/4/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
9/4/2013	13:30 - 15:00	1.50	SUBSPR	30	A	P		MIRU, ND WH, NU BOP'S, RU FLOOR & TBG EQUIP, SPOT IN TBG TRAILER
	15:00 - 17:00	2.00	SUBSPR	31	I	P		P/U 3-7/8" MILL, TIH W/ 2-3/8" TBG, TAG CEMENT TOP @ 5017', SDFN
9/5/2013	6:45 - 7:00	0.25	SUBSPR	48		P		HSM, JSA
	7:00 - 9:30	2.50	SUBSPR	44	B	P		MIRU PWR SWVL, D/O CEMENT FROM 5017' TO 5086', D/O DV TOOL @ 5086'
	9:30 - 11:30	2.00	SUBSPR	31	I	P		P/U TBG, TIH TAG UP @ 9927'
	11:30 - 14:30	3.00	SUBSPR	44	D	P		C/O FROM 9927' TO 9942'(16' ABOVE PBTD), MILL KEPT PLUGING UP & WOULDENT GO ANY DEEPER
	14:30 - 18:30	4.00	SUBSPR	31	I	P		TOOH & LD 2-3/8" TBG ON TRAILER, LD 3-7/8" MILL, SDFN
9/12/2013	-							
9/18/2013	9:00 - 10:00	1.00	SUBSPR	52	B	P		FILL SURFACE CSG. MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & FRAC VALVES 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST 60 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI. PRESSURE TEST 8 5/8 X 4 1/2 TO 538 PSI HELD FOR 5 MIN LOST -377 PSI,BLED PSI OFF, REINSTALLED POP OFF SWIFN NO PRESSURE ON SURFACE CASING FILLED SURFACE WITH 1 BBL H2O
9/19/2013	10:00 - 11:00	1.00	SUBSPR	37		P		PERF STG 1)PU 3 1/8 EXP GUN, 19 GM, .40 HOLE SIZE. RIH PERFWELL, AS PER PERF DESIGN. POOH. SWIFW
9/23/2013	7:00 - 7:15	0.25	FRAC	48		P		HSM-JSA
	7:15 - 17:00	9.75	FRAC	36	H	P		FRAC STG #1)WHP 1659 PSI, BRK 3175 PSI @ 4.3 BPM. ISIP 2565 PSI, FG. 0.7 ISIP 3054 PSI, FG. 0.75, NPI 489 PSI, X/O TO WL. SET CBP & PERF STG #2 AS DESIGNED, X/O TO FRAC. FRAC STG #2)WHP 626 PSI, BRK 3805 PSI @ 4.6 BPM. ISIP 2979 PSI, FG. 0.75 ISIP 2979 PSI, FG. 0.75, NPI 0 PSI, SWI, SDFN.
9/24/2013	7:00 - 7:15	0.25	FRAC	48		P		HSM-JSA

RECEIVED: Oct. 31, 2013

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW		Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD		Rig Name No: SWABBCO 6/6
Event: COMPLETION	Start Date: 9/4/2013		End Date: 10/4/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 17:30	10.25	FRAC	36	H	P		SET CBP & PERF STG #3 AS DESIGNED, X/O TO FRAC. FRAC STG #3)WHP 1475 PSI, BRK 5408 PSI @ 4.3 BPM. ISIP 2929 PSI, FG. 0.75 ISIP 2939 PSI, FG. 0.75, NPI 10 PSI, X/O TO WL. SET CBP & PERF STG #4 AS DESIGNED, X/O TO FRAC. FRAC STG#4)WHP 2416 PSI, BRK 4144 PSI @ 3.4 BPM. ISIP 2922 PSI, FG. 0.76 ISIP 2961 PSI, FG. 0.77, NPI 39 PSI, SWI, SDFN.
9/25/2013	7:00 - 7:15	0.25	FRAC	48		P		HSM-JSA
	7:15 - 17:30	10.25	FRAC	36	H	P		SET CBP & PERF STG #5 AS DESIGNED, X/O TO FRAC. FRAC STG #5)WHP 1197 PSI, BRK 4200 PSI @ 4.4 BPM. ISIP 2668 PSI, FG. 0.74 ISIP 2934 PSI, FG. 0.77, NPI 266 PSI, X/O TO WL. SET CBP & PERF STG #6 AS DESIGNED, X/O TO FRAC. FRAC STG #6)WHP 1394 PSI, BRK 4778 PSI @ 4.4 BPM. ISIP 3324 PSI, FG. 0.83 ISIP 2386 PSI, FG. 0.72, NPI -938 PSI, X/O TO WL. SET CBP & PERF STG #7 AS DESIGNED, X/O TO FRAC. FRAC STG #7)WHP 1210 PSI, BRK 3488 PSI @ 4.7 BPM. ISIP 2040 PSI, FG. 0.69 ISIP 2508 PSI, FG. 0.75, NPI 468 PSI, SWI, SDFN.
9/26/2013	7:00 - 7:15	0.25	FRAC	48		P		HSM-JSA
	7:15 - 12:00	4.75	FRAC	36	H	P		SET CBP & PERF STG #8 AS DESIGNED, X/O TO FRAC. FRAC STG #8)WHP 1125 PSI, BRK 2672 PSI @ 4.6 BPM. ISIP 1815 PSI, FG. 0.67 ISIP 2823 PSI, FG. 0.78, NPI 1008 PSI, X/O TO WL. SET KILL PLUG @ 7828' RDMO FRAC EQUIP & WIRELINE. TOTAL CLN FLUID PUMPED=12072 BBLS TOTAL SAND PUMPED=248965 LBS
10/3/2013	7:00 - 7:30	0.50	DRLOUT	48		P		PU TBG
	7:30 - 15:00	7.50	DRLOUT	31	I	P		MIRU,NDWH, NU 3" FLOW LINE TO PIT, DRAIN LINE FOR SPILL BOWL, NU BOP'S, TEST BOP'S, 3000#, PU SN, POBS, BIT, TBG, TIH TBG 249 JTS, 7826', TAG KILL CBP. PU PWR SWIVEL, BREAK CIRC, SWIFN
10/4/2013	7:00 - 7:30	0.50	DRLOUT	48		P		POBS

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-22H1CS YELLOW	Spud Date: 3/19/2013	
Project: UTAH-UINTAH	Site: NBU 921-22H PAD	Rig Name No: SWABBCO 6/6
Event: COMPLETION	Start Date: 9/4/2013	End Date: 10/4/2013
Active Datum: RKB @4,850.00usft (above Mean Sea Level)	UWI: SE/NE/0/9/S/21/E/22/0/0/26/PM/N/2179/E/0/637/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:30 - 16:00	8.50	DRLOUT	44	C	P		MILL 8 PLUGS, 9671', 312JTS, TIH TO 9958' 314 JTS, C/O 90' SAND, POOH TO 297 JTS 9414.79', LAND TBG, ND BOP'S, NUWH, POBS, 2100#, TEST FLOW LINE TO 3000#, RDMO PLUG# 1 7826' 10' SAND 11 MIN 0# KICK PLUG# 2 8082' 20' SAND 8 MIN 50# KICK PLUG# 3 8286' 60' SAND 8 MIN 100# KICK PLUG# 4 8605' 60' SAND 8 MIN 100# KICK PLUG# 5 8898' 30' SAND 9 MIN 100# KICK PLUG# 6 9171' 30' SAND 10 MIN 100# KICK PLUG# 7 9434' 30' SAND 9 MIN 50# KICK PLUG# 8 9671' 15' SAND 13 MIN 100# KICK PBTD 9954.91' BTM PERF 9834' TBG 147 JTS L-80 4643.36' TBG 150 JTS J-55 4744.40' KB 24.00' HANGER 4.125" .83' SN 1.875" 2.20' EOT 9414.79' 6' PUP JT 4662.19' - 4668.19' FRAC WTR 12,072 BBLS RCVD 2,500 BBLS LTR 9,572 BBLS

API Well Number: 43047526500000

Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-22H PAD
Well: NBU 921-22H1CS
Wellbore: OH
Design: OH

Scientific Drilling

Anadarko Petroleum Corporation

WELL DETAILS: NBU 921-22H1CS					
GL 4826 & KB 24 @ 4850.00ft (H&P 318)					
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14537772.47	2051971.43	40.022883	-109.530005



Azimuths to True North
Magnetic North: 11.03°

Magnetic Field
Strength: 52290.9snT
Dip Angle: 65.87°
Date: 2011/12/06
Model: IGRF2010





PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N	
Geodetic System:	Universal Transverse Mercator (US Survey Feet)
Datum:	NAD 1927 (NADCON CONUS)
Ellipsoid:	Clarke 1866
Zone:	Zone 12N (114 W to 108 W)
Location:	SECTION 22 T9S R21E
System Datum:	Mean Sea Level

Design: OH (NBU 921-22H1CS/OH)
Created By: Gabe Kendall Date: 15:48, August 08 2013

API Well Number: 43047526500000

Scientific Drilling

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N
NBU 921-22H PAD
NBU 921-22H1CS

OH

Design: OH

Standard Survey Report

08 August, 2013

Anadarko Petroleum Corporation

RECEIVED: Oct. 31, 2013

Scientific Drilling

SDI
Survey Report

Anadarko Petroleum Corporation

Company:	US ROCKIES REGION PLANNING	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	**TVD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Site:	NBU 921-22H PAD	**MD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Well:	NBU 921-22H1CS	**North Reference:**	True
Wellbore:	OH	**Survey Calculation Method:**	Minimum Curvature
Design:	OH	**Database:**	EDM 5000.1 Single User Db

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System:	Universal Transverse Mercator (US Survey Feet)	**System Datum:**	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site NBU 921-22H PAD, SECTION 22 T9S R21E

Site Position:		**Northing:**	14,537,789.42 usft	**Latitude:**	40.022930
From:	Lat/Long	**Easting:**	2,051,961.07 usft	**Longitude:**	-109.530041
Position Uncertainty:	0.00 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	0.95 °

Well NBU 921-22H1CS, 2179 FNL 637 FEL

Well Position	**+N/-S**	0.00 ft	**Northing:**	14,537,772.48 usft	**Latitude:**	40.022883
	+E/-W	0.00 ft	**Easting:**	2,051,971.43 usft	**Longitude:**	-109.530005
Position Uncertainty		0.00 ft	**Wellhead Elevation:**	ft	**Ground Level:**	4,826.00 ft

Wellbore OH

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2011/12/06	11.03	65.87	52,291

Design OH

Audit Notes:

Version:	1.0	**Phase:**	ACTUAL	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	18.03

Survey Program **Date** 2013/08/08

From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
20.00	2,855.00	Survey #1 SDI MWD SURFACE (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1
2,951.00	10,040.00	Survey #2 SDI MWD PRODUCTION (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
20.00	0.00	0.00	20.00	0.00	0.00	0.00	0.00	0.00	0.00
204.00	0.41	253.50	204.00	-0.19	-0.63	-0.37	0.22	0.22	0.00
FIRST SDI MWD SURFACE SURVEY									
287.00	0.70	339.66	287.00	0.20	-1.09	-0.14	0.95	0.35	103.81
375.00	2.46	13.33	374.96	2.55	-0.84	2.16	2.18	2.00	38.26
465.00	5.01	16.58	464.76	8.19	0.72	8.01	2.84	2.83	3.61
555.00	7.03	17.55	554.26	17.21	3.51	17.45	2.25	2.24	1.08
645.00	7.83	15.35	643.50	28.37	6.79	29.08	0.94	0.89	-2.44
735.00	8.44	19.13	732.60	40.53	10.58	41.81	0.90	0.68	4.20

Scientific Drilling

SDI
Survey Report

Anadarko Petroleum Corporation

Company:	US ROCKIES REGION PLANNING	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	**TVD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Site:	NBU 921-22H PAD	**MD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Well:	NBU 921-22H1CS	**North Reference:**	True
Wellbore:	OH	**Survey Calculation Method:**	Minimum Curvature
Design:	OH	**Database:**	EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
825.00	8.79	20.18	821.58	53.22	15.11	55.29	0.43	0.39	1.17
915.00	9.23	20.27	910.47	66.45	19.99	69.37	0.49	0.49	0.10
1,005.00	9.85	20.27	999.23	80.44	25.15	84.27	0.69	0.69	0.00
1,095.00	9.94	15.88	1,087.89	95.13	29.95	99.73	0.84	0.10	-4.88
1,185.00	10.35	14.19	1,176.48	110.44	34.05	115.56	0.56	0.46	-1.88
1,275.00	9.76	14.38	1,265.10	125.67	37.93	131.24	0.66	-0.66	0.21
1,365.00	9.15	16.93	1,353.88	139.90	41.91	146.01	0.82	-0.68	2.83
1,455.00	8.35	15.96	1,442.83	153.03	45.79	159.69	0.90	-0.89	-1.08
1,545.00	8.88	16.14	1,531.81	165.99	49.52	173.16	0.59	0.59	0.20
1,635.00	9.56	12.00	1,620.65	179.97	53.00	187.54	1.06	0.76	-4.60
1,725.00	10.29	8.23	1,709.30	195.24	55.71	202.89	1.09	0.81	-4.19
1,815.00	10.38	12.54	1,797.85	211.11	58.62	218.89	0.86	0.10	4.79
1,905.00	9.44	15.46	1,886.50	226.14	62.35	234.33	1.18	-1.04	3.24
1,995.00	9.41	14.29	1,975.29	240.38	66.13	249.05	0.22	-0.03	-1.30
2,085.00	10.11	11.74	2,063.98	255.25	69.55	264.24	0.91	0.78	-2.83
2,175.00	9.32	12.80	2,152.69	270.09	72.77	279.35	0.90	-0.88	1.18
2,265.00	8.44	12.62	2,241.61	283.64	75.83	293.18	0.98	-0.98	-0.20
2,355.00	7.83	15.88	2,330.71	295.98	78.95	305.88	0.85	-0.68	3.62
2,445.00	8.53	16.05	2,419.79	308.29	82.48	318.68	0.78	0.78	0.19
2,535.00	10.46	21.68	2,508.56	322.30	87.34	333.51	2.38	2.14	6.26
2,625.00	10.26	21.87	2,597.09	337.33	93.34	349.66	0.23	-0.22	0.21
2,715.00	9.23	19.30	2,685.79	351.58	98.72	364.87	1.24	-1.14	-2.86
2,805.00	7.91	14.30	2,774.78	364.39	102.63	378.27	1.68	-1.47	-5.56
2,855.00	8.71	15.61	2,824.26	371.37	104.50	385.48	1.64	1.60	2.62
LAST SDI MWD SURFACE SURVEY									
2,951.00	9.41	12.76	2,919.06	386.03	108.19	400.56	0.87	0.73	-2.97
FIRST SDI MWD PRODUCTION SURVEY									
3,045.00	8.58	8.57	3,011.91	400.46	110.93	415.13	1.12	-0.88	-4.46
3,140.00	7.85	5.32	3,105.93	413.93	112.59	428.45	0.91	-0.77	-3.42
3,234.00	7.00	8.05	3,199.14	425.99	113.99	440.35	0.98	-0.90	2.90
3,328.00	6.21	14.02	3,292.52	436.59	116.02	451.06	1.11	-0.84	6.35
3,423.00	4.79	17.55	3,387.08	445.36	118.46	460.16	1.54	-1.49	3.72
3,517.00	3.50	9.07	3,480.83	451.94	120.10	466.92	1.52	-1.37	-9.02
3,612.00	1.91	20.73	3,575.72	456.28	121.11	471.36	1.76	-1.67	12.27
3,706.00	0.45	70.28	3,669.70	457.87	122.02	473.15	1.76	-1.55	52.71
3,800.00	0.52	98.11	3,763.70	457.94	122.79	473.45	0.26	0.07	29.61
3,895.00	0.26	148.20	3,858.70	457.69	123.33	473.39	0.43	-0.27	52.73
3,989.00	0.62	162.71	3,952.69	457.02	123.59	472.84	0.40	0.38	15.44
4,084.00	0.78	179.30	4,047.69	455.89	123.75	471.80	0.27	0.17	17.46
4,178.00	0.80	184.14	4,141.68	454.59	123.71	470.56	0.07	0.02	5.15
4,272.00	0.67	209.78	4,235.67	453.46	123.39	469.39	0.37	-0.14	27.28
4,366.00	0.93	195.22	4,329.66	452.25	122.92	468.09	0.35	0.28	-15.49
4,461.00	0.26	265.18	4,424.66	451.49	122.50	467.23	0.92	-0.71	73.64

Scientific Drilling

SDI

Survey Report

Anadarko Petroleum Corporation

Company:	US ROCKIES REGION PLANNING	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	**TVD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Site:	NBU 921-22H PAD	**MD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Well:	NBU 921-22H1CS	**North Reference:**	True
Wellbore:	OH	**Survey Calculation Method:**	Minimum Curvature
Design:	OH	**Database:**	EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,555.00	0.09	40.53	4,518.66	451.52	122.34	467.22	0.35	-0.18	143.99
4,650.00	0.09	133.61	4,613.66	451.53	122.44	467.25	0.14	0.00	97.98
4,744.00	0.35	109.70	4,707.66	451.38	122.76	467.21	0.29	0.28	-25.44
4,838.00	0.53	153.12	4,801.65	450.90	123.23	466.90	0.39	0.19	46.19
4,932.00	0.44	180.81	4,895.65	450.15	123.42	466.24	0.26	-0.10	29.46
5,027.00	1.06	41.15	4,990.65	450.45	123.99	466.70	1.50	0.65	-147.01
5,121.00	0.88	36.93	5,084.63	451.68	125.00	468.19	0.21	-0.19	-4.49
5,216.00	0.70	59.52	5,179.62	452.55	125.94	469.31	0.38	-0.19	23.78
5,310.00	0.35	56.18	5,273.62	453.01	126.67	469.97	0.37	-0.37	-3.55
5,405.00	0.53	94.76	5,368.62	453.13	127.35	470.30	0.35	0.19	40.61
5,499.00	0.53	109.26	5,462.61	452.95	128.19	470.39	0.14	0.00	15.43
5,594.00	0.64	98.45	5,557.61	452.73	129.13	470.47	0.16	0.12	-11.38
5,688.00	0.62	119.81	5,651.60	452.40	130.09	470.45	0.25	-0.02	22.72
5,783.00	0.97	351.40	5,746.60	452.94	130.42	471.06	1.52	0.37	-135.17
5,877.00	1.06	333.65	5,840.58	454.50	129.91	472.40	0.35	0.10	-18.88
5,972.00	1.14	341.47	5,935.57	456.19	129.22	473.78	0.18	0.08	8.23
6,066.00	0.44	114.36	6,029.56	456.93	129.26	474.49	1.57	-0.74	141.37
6,161.00	0.44	116.47	6,124.56	456.61	129.91	474.40	0.02	0.00	2.22
6,255.00	0.69	141.03	6,218.55	456.01	130.59	474.04	0.36	0.27	26.13
6,350.00	0.80	149.77	6,313.54	454.99	131.29	473.29	0.17	0.12	9.20
6,444.00	1.12	151.17	6,407.53	453.62	132.06	472.22	0.34	0.34	1.49
6,539.00	0.31	208.86	6,502.52	452.58	132.38	471.33	1.04	-0.85	60.73
6,633.00	0.65	284.69	6,596.52	452.50	131.75	471.05	0.69	0.36	80.67
6,727.00	0.60	279.02	6,690.52	452.71	130.74	470.94	0.08	-0.05	-6.03
6,822.00	0.38	244.79	6,785.51	452.65	129.97	470.65	0.38	-0.23	-36.03
6,916.00	0.47	196.39	6,879.51	452.15	129.58	470.05	0.38	0.10	-51.49
7,010.00	0.60	173.61	6,973.51	451.29	129.52	469.22	0.26	0.14	-24.23
7,105.00	0.65	179.67	7,068.50	450.26	129.58	468.25	0.09	0.05	6.38
7,199.00	0.44	49.06	7,162.50	449.96	129.86	468.06	1.06	-0.22	-138.95
7,293.00	0.52	48.56	7,256.49	450.48	130.45	468.73	0.09	0.09	-0.53
7,388.00	0.35	88.17	7,351.49	450.77	131.06	469.20	0.35	-0.18	41.69
7,482.00	0.35	85.89	7,445.49	450.80	131.64	469.41	0.01	0.00	-2.43
7,577.00	0.64	359.15	7,540.49	451.35	131.92	470.02	0.75	0.31	-91.31
7,671.00	0.62	19.99	7,634.48	452.36	132.08	471.03	0.24	-0.02	22.17
7,766.00	0.40	49.22	7,729.48	453.06	132.51	471.82	0.35	-0.23	30.77
7,860.00	0.35	91.16	7,823.48	453.27	133.05	472.19	0.29	-0.05	44.62
7,955.00	0.23	101.44	7,918.48	453.22	133.52	472.29	0.14	-0.13	10.82
8,049.00	0.60	110.20	8,012.47	453.01	134.17	472.30	0.40	0.39	9.32
8,144.00	0.53	292.60	8,107.47	453.01	134.23	472.31	1.19	-0.07	-186.95
8,238.00	0.17	278.56	8,201.47	453.20	133.69	472.32	0.39	-0.38	-14.94
8,332.00	0.24	238.99	8,295.47	453.12	133.38	472.15	0.16	0.07	-42.10
8,427.00	0.54	184.40	8,390.47	452.57	133.18	471.57	0.47	0.32	-57.46
8,521.00	0.21	36.93	8,484.47	452.27	133.25	471.30	0.77	-0.35	-156.88
8,615.00	0.36	71.44	8,578.46	452.50	133.63	471.64	0.24	0.16	36.71

Scientific Drilling

SDI
Survey Report

Anadarko Petroleum Corporation

Company:	US ROCKIES REGION PLANNING	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	**TVD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Site:	NBU 921-22H PAD	**MD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Well:	NBU 921-22H1CS	**North Reference:**	True
Wellbore:	OH	**Survey Calculation Method:**	Minimum Curvature
Design:	OH	**Database:**	EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,710.00	0.35	101.44	8,673.46	452.54	134.20	471.85	0.19	-0.01	31.58
8,804.00	0.30	82.91	8,767.46	452.51	134.73	471.99	0.12	-0.05	-19.71
8,898.00	0.47	113.15	8,861.46	452.39	135.32	472.06	0.28	0.18	32.17
8,993.00	0.69	119.68	8,956.45	451.95	136.18	471.91	0.24	0.23	6.87
9,087.00	0.95	128.45	9,050.44	451.19	137.28	471.52	0.31	0.28	9.33
9,181.00	0.27	176.87	9,144.44	450.48	137.90	471.04	0.85	-0.72	51.51
9,276.00	0.35	160.94	9,239.44	449.98	138.01	470.60	0.12	0.08	-16.77
9,370.00	0.81	152.29	9,333.43	449.12	138.41	469.91	0.50	0.49	-9.20
9,465.00	1.01	165.30	9,428.42	447.72	138.94	468.74	0.30	0.21	13.69
9,559.00	0.81	187.37	9,522.41	446.26	139.06	467.39	0.43	-0.21	23.48
9,653.00	1.09	183.18	9,616.40	444.71	138.93	465.87	0.31	0.30	-4.46
9,748.00	0.98	163.63	9,711.38	443.03	139.11	464.33	0.39	-0.12	-20.58
9,842.00	1.07	157.47	9,805.37	441.44	139.67	463.00	0.15	0.10	-6.55
9,936.00	1.50	154.92	9,899.34	439.52	140.53	461.43	0.46	0.46	-2.71
9,982.00	1.88	149.47	9,945.32	438.32	141.17	460.49	0.90	0.83	-11.85
LAST SDI MWD PRODUCTION SURVEY									
10,040.00	1.88	149.47	10,003.29	436.68	142.13	459.23	0.00	0.00	0.00
SDI PROJECTION TO BIT									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
DTGT_NBU 921-22H1C	0.00	0.00	3,697.00	464.23	126.69	14,538,238.73	2,052,090.44	40.024158	-109.529553
- actual wellpath misses target center by 7.72ft at 3733.34ft MD (3697.04 TVD, 457.93 N, 122.22 E)									
- Circle (radius 15.00)									
TOC @ 5494.00 NBU 92	0.00	0.00	5,494.00	456.96	131.05	14,538,231.53	2,052,094.92	40.024138	-109.529537
- actual wellpath misses target center by 4.84ft at 5530.40ft MD (5494.02 TVD, 452.86 N, 128.48 E)									
- Point									
PBHL_NBU 921-22H1C	0.00	0.00	10,003.00	439.23	141.69	14,538,213.99	2,052,105.85	40.024089	-109.529499
- actual wellpath misses target center by 2.58ft at 10039.63ft MD (10002.92 TVD, 436.69 N, 142.13 E)									
- Circle (radius 25.00)									

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
204.00	204.00	-0.19	-0.63	FIRST SDI MWD SURFACE SURVEY
2,855.00	2,824.26	371.37	104.50	LAST SDI MWD SURFACE SURVEY
2,951.00	2,919.06	386.03	108.19	FIRST SDI MWD PRODUCTION SURVEY
9,982.00	9,945.32	438.32	141.17	LAST SDI MWD PRODUCTION SURVEY
10,040.00	10,003.29	436.68	142.13	SDI PROJECTION TO BIT

Scientific Drilling

SDI

Survey Report

Anadarko Petroleum Corporation

Company:	US ROCKIES REGION PLANNING	**Local Co-ordinate Reference:**	Well NBU 921-22H1CS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	**TVD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Site:	NBU 921-22H PAD	**MD Reference:**	GL 4826 & KB 24 @ 4850.00ft (H&P 318)
Well:	NBU 921-22H1CS	**North Reference:**	True
Wellbore:	OH	**Survey Calculation Method:**	Minimum Curvature
Design:	OH	**Database:**	EDM 5000.1 Single User Db

Checked By: _____ Approved By: _____ Date: _____